

## **Historic, Archive Document**


Do not assume content reflects current scientific knowledge, policies, or practices.



Reserve  
aTC424  
.C6F58

FLOOD PLAIN MANAGEMENT  
STUDY

TOWN OF SILT



COLORADO

Prepared by the  
U.S. Department of Agriculture  
Soil Conservation Service  
Denver, Colorado  
in cooperation with the  
Colorado Water Conservation Board  
Town of Silt  
and Garfield County, Colorado  
July 1987

AD-83 Bookplate  
(1-83)

**NATIONAL**

**A  
G  
R  
I  
C  
U  
L  
T  
U  
R  
A  
L**



**LIBRARY**

## PREFACE

This report includes information on the flood hazard areas along five Colorado River Tributaries in the vicinity of Silt, Colorado.

Because of the potential flood damages, detailed flood hazard studies have been recognized as an essential item in guiding the use of flood plains. The purpose of this report is to provide adequate mapping and data for implementing flood plain management programs.

Included in the report is information on past floods, the potential for future floods, flooded area maps, water surface profiles, selected cross sections, peak discharge data, and recommendations for reducing potential flood damages.

The Soil Conservation Service conducted the technical studies and prepared the report. These services were carried out in accordance with the Plan of Work of March 1985.

The assistance and cooperation provided by the Colorado Water Conservation Board, Town of Silt and Garfield County are appreciated and gratefully acknowledged. Financial assistance provided by the Board, the town and county included funds for photogrammetric maps, and cross section data.

The survey, hydrologic, hydraulic, and other pertinent data and computations are on file with the U.S. Department of Agriculture, Soil Conservation Service, 2490 West 26th Avenue, Denver, Colorado 80217, telephone (303) 964-0295. Additional copies of this report may be obtained from the Colorado Water Conservation Board, or the Soil Conservation Service.

U.S. DEPT. OF AGRICULTURE  
NATIONAL AGRICULTURAL LIBRARY

CALCO 10-1-85



## TABLE OF CONTENTS

	Page
INTRODUCTION	1
DESCRIPTION OF STUDY AREA	4
Basin Characteristics	
Study Limits	
Natural and Beneficial Flood Plain Values	
RELATED FLOOD STUDIES	8
FLOOD HISTORY	9
INVESTIGATIONS AND ANALYSIS	11
Interpretation and Use of Report	
Hydrology	
Hydraulics	
FLOOD PLAIN MANAGEMENT	16
Local Regulations	
Colorado Natural Hazard Area Regulations	
Colorado Water Conservation Board Designations	
Model Regulations	
Flood Insurance	
Flood Warning and Flood Forecasting Systems	
Evacuation Plan	
Structural Flood Control Measures	
RECOMMENDATIONS	26
GLOSSARY OF TERMS	27
BIBLIOGRAPHY AND REFERENCES	30
APPENDIX - Separate Document Showing Floodway Tables	





## LIST OF TABLES, MAPS, EXHIBITS

	Page
Drainage Basin Map	6
Structural Measures	25
Comparison of Alternatives	25
Index Map	32
Flood Plain Maps	Sheets 1 - 14
Flood Profiles	Sheets 1 - 23
Typical Valley Cross Sections	Fig. 1 - 4
Flood Frequency - Elevation - Discharge Data (Table 1)	Pgs. 1 - 18



# FLOOD PLAIN MANAGEMENT STUDY

## TOWN OF SILT

### COLORADO

## INTRODUCTION

This flood plain management report was prepared by the U.S. Department of Agriculture, Soil Conservation Service, in cooperation with the Colorado Water Conservation Board, Town of Silt and Garfield County. Interpretations of the flood plain management study and recommendations to reduce damages are included.

### Objectives

The objective of this study is to provide flood plain management information and mapping to the Town of Silt and Garfield County for use in implementing flood plain management programs which will minimize potential flood losses. Included in the report are engineering and hydrologic data which will facilitate the development of a flood plain management plan, road and bridge designs, and flood control measures (if needed).

### Authority

This study was requested by the Town of Silt and Garfield County through the Colorado Water Conservation Board (CWCB). The CWCB is the state coordinator for all flood plain information studies and is responsible for setting priorities and scheduling these studies. The CWCB and the Soil Conservation Service entered into a Joint Coordination Agreement for flood hazard analyses in January 1972 (revised November 1978). The Plan of Work for the study was prepared in March, 1985.

Section 37-60-106(1)(c), Colorado Revised Statutes, authorizes the Colorado Water Conservation Board "to designate and approve storm or floodwater runoff channels or basins, and to make such designations available to legislative bodies of cities and incorporated towns, to county planning commissions, and to boards of adjustment of cities, incorporated towns, and counties of this state." The Board provides assistance to local governments in development and adoption of effective floodplain ordinances. In addition, the Board will provide technical assistance to local entities during the performance of floodplain information studies within Colorado. Presently, direct financial assistance for the performance of floodplain studies is no longer available from the board.

Section 30-28-111 C.R.S. for county governments and Section 31-23-301 C.R.S. for municipal governments of the Colorado Revised Statutes, states: The cities, incorporated towns, and counties within the study area may provide zoning regulations: "...to establish, regulate, restrict, and limit such uses on or along any storm or floodwater runoff channel or basin that has been designated and approved by the Colorado Water Conservation Board, in order to lessen or avoid the hazards to persons and damage to property resulting from the accumulation of storm or floodwaters..."

Therefore, upon official approval of this report by the Colorado Water Conservation Board, the areas described as being inundated by the 100-year flood can be designated as flood hazard areas and their use regulated accordingly by the local agencies.

Flood plain management studies are carried out by the Soil Conservation Service as an outgrowth of the recommendations in A Report by

the Task Force on Federal Flood Control Policy, House Document No. 465 (89th Congress, August 10, 1966), especially Recommendation 9(c), Regulation of Land Use, which recommended the preparation of preliminary reports for guidance in those areas where assistance is needed before a full flood plain information report can be prepared or where a full report is not scheduled.

Authority for funding flood plain management studies is provided by Section 6 of Public Law 83-566, which authorizes the U.S. Department of Agriculture to cooperate with other federal, state and local agencies to make investigations and surveys of the watersheds and rivers and other waterways as a basis for the development of coordinated programs. In carrying out flood plain management studies, the Soil Conservation Service is being responsive to Executive Order 11988, entitled "Flood Plain Management", and Executive Order 11990, entitled "Protection of Wetlands" (both effective May 24, 1977).

## DESCRIPTION OF THE STUDY AREA

### Basin Characteristics

This study involves five tributaries to the Colorado River totaling about 17.6 miles of stream. The tributaries are located north of the Colorado River. Their northern boundaries reach an elevation of about 7,800 feet along the Grand Hogback north of Silt. These tributaries flow in a southerly direction through the town of Silt then on to the Colorado River at an elevation of about 5,400 feet.

The topography is primarily a hogback cut by watercourses which form steep canyons. They open on to alluvial fans which provide the setting for the town of Silt.

The climate of the area is influenced by Pacific storm systems that move from west to east. The nearest national weather station, representative of the study area, is at Rifle. The mean annual temperature is 47°F with about 109 days of growing season between the spring and fall 32°F frost occurrences. The mean annual precipitation is just over 11 inches. This increases to about 12 inches at the higher elevations of the northern boundaries. Wintertime precipitation is usually in the form of snow during October to early April.

The soils include Torriorthents-Rock Outcrop at the higher elevations and Potts, Ildefonso, and Olney in the lower part of the basins. The geologic formations include sandstones of the Mesaverde along the hogback and Wasatch South of the hogback.

The higher ridges have pinyon and juniper interspersed with sagebrush. Willows and cottonwoods grow along the streams. There is a considerable amount of irrigated pasture and cropland along the middle and lower reaches of the basins.

An irrigation canal (Lower Cactus Valley Ditch) flows in a westerly direction through the town of Silt. Four of the drainages studied herein are intercepted by this canal. The canal flows through an inverted siphon under the fifth tributary (West Basin).


The town of Silt is the only community in the study area.

#### Study Limits

The area of study includes listed stream reach distances along the following tributaries:

<u>Tributary</u>	<u>Stream Reach</u>
West Basin	4.16 miles
First Street Basin	4.21
Seventh Street Basin	1.41
Sixteenth Street Basin	3.85
East Basin	<u>3.96</u>
Total	17.59





DRAINAGE BASIN MAP  
TOWN OF SILT  
FLOOD PLAIN MANAGEMENT STUDY



### Natural and beneficial Flood Plain Values

Flood plains along the various tributaries contain areas of irrigated pasture and hayland interspersed with areas of natural vegetation. The flood plain vegetation consists of a variety of forbs, grasses, sedges and rushes interspersed with cottonwoods, willows and siberian elm. The meandering channel provides an interesting diversity in landscape and vegetation. This diversity enhances the visual aesthetics and wildlife habitat values in the area.

These flood plains support a variety of wildlife species such as: mule deer, coyote, cottontail, red-winged blackbird, blue heron, song sparrow, black-headed grosbeak, red-tailed hawk, golden eagle, bald eagle, Canada goose, mallard and many other species of wildlife. These riparian areas are very important in the arid regions of Colorado. The proximity to water and robust vegetation supported by the water regime attract more species of wildlife to this habitat type than any other in western Colorado.

## RELATED FLOOD STUDIES

The Corps of Engineers, Sacramento District, prepared an Internal Official Memorandum Report "Flood Insurance Study Hydrology, Garfield and Mesa Counties, Colorado" dated November 1975. This was a relatively broad study that included drainage area vs. cubic feet per second per square mile envelope curves. The curves were intended for estimating peak discharges on streams in Garfield and Mesa Counties, Colorado, for flood insurance purposes.

The Corps of Engineers, Sacramento District, prepared a flood plain information report "Colorado River and Rifle, Government, and Hubbard Gulch Creeks" (Apr 1973). The Corps is currently involved in an additional study of the Colorado River Main Stem that extends beyond the limits of this 1973 study.

The Soil Conservation Service carried out a Flood Plain Management Study on Parachute Creek and Roan Creek (Aug 1985).

The Soil Conservation Service carried out a Flood Plain Management Study on 10 tributaries to the Colorado River in the vicinity of Glenwood Springs and New Castle (July 1986).

The Federal Emergency Management Agency published a flood insurance study for Garfield County, unincorporated areas (Jan 3, 1986).

## FLOOD HISTORY

Minor flooding along streams in this study is caused by rapid melting of the snowpack during late May to early July. The major flood threat is from summer rainstorms. There is also the potential for flooding as a result of rainfall occurring on melting snow. The snowmelt floods are characterized by moderate peaks, large volumes, and long durations. The summer floods have characteristics of high peaks, short flow durations, and relatively small volumes.

The size of drainage area varies from Seventh Street Basin (0.38 square miles) to West Basin (4.39 square miles). The West Basin Drainage area does not include that portion above Grass Valley Reservoir Dam. It was determined that drainage into the reservoir would not contribute significantly to peak discharges below the dam for the 100-year and 500-year flood events.

There is no published history of flooding in Silt, however, field observations and interviews indicate flooding has occurred in the past.

Local residents have stated that runoff from snowmelt or summer rainstorms is intercepted by the Lower Cactus Valley Ditch. The ditch conveys this runoff to locations where the bank is low in elevation at which point overflow occurs. Some homes immediately above the ditch, as well as properties below the ditch, receive damage due to the overflow. The north-south streets serve as a conveyance facility; however, the east-west streets cause backwater and deflect the flows laterally to other locations. The depth of flooding in most locations is shallow because of the steep topography and relatively small contributing drainage areas.

A few homes immediately below the canal have received damage from ground water seepage not directly related to flooding.

There is a potential for considerable flood damage from floods in the 50 year and 100 year magnitude. The type of flooding expected from these events would be numerous small damage sites throughout the town which would add up to major losses. Since historical flood records are not available, the following table shows the expected flood discharges for several frequencies and locations:

----- EXPECTED FLOOD DISCHARGES -----			
Location	Discharge - cfs		
	10 yr.	50 yr.	100 yr.
-----			
West Basin			
At Lower Cactus V. Ditch	169	463	633
First St. Basin			
At County Rd 231	107	353	488
Seventh Street Basin			
At Orchard Avenue	6	32	53
Sixteenth Street Basin			
At Ware & Hinds Ditch	60	178	237
East Basin			
At Ware & Hinds Ditch	59	162	215

## INVESTIGATIONS AND ANALYSIS

### Interpretation and Use of Report

#### A. Frequency and Discharge

The 10-, 50-, 100-, and 500-year flood events are used as the flood frequencies for this flood plain analysis. Thus, the data developed in this report will be suitable not only for regulation purposes, and H.B. 1041 designation but also for Federal Insurance Administration flood insurance studies conducted by the Federal Emergency Management Agency.

These various flood events have an average occurrence of once in the number of years as indicated. For example, the 100-year flood occurs, on the average, once in a 100-year period, and has a one percent chance of being equaled or exceeded in any given year.

The particular uses for the various flood events in addition to those stated above are as follows:

#### 10-Year and 50-Year Flood Events

Information regarding these lower frequency floods is especially useful for future engineering studies and land use planning purposes related to minor road systems, minor channel improvements, the location of parks and recreational facilities, agricultural lands, and appurtenant structures. The use of the lower frequency floods may be considered in planning flood prevention projects to protect agricultural areas, or other property where risk to life is not a factor.

#### 100-Year Flood Event

The 100-year flood event may be used in lieu of lower frequencies for engineering design purposes where greater security from structure failure is desired.



However, the most important use of the 100-year flood event lies in flood plain management and land use planning as set forth in the state statutes. The State of Colorado considers the 100-year frequency flood as the flood event to be used in designing and protecting structures and dwellings for human occupation. Therefore, all flood plain regulations are based upon the 100-year flood.

#### 500-Year Flood Event

The 500-year flood event is useful in making the public aware that floods larger than the 100-year flood can and do occur. Just because a person is living above the 100-year flood boundary does not mean that he is completely safe from flooding. The 500-year flood event can also be used for regulating high risk developments within the flood plain such as nuclear power plants, or the storage or manufacture of toxic or explosive materials.

#### B. Flood Elevation

Flood crest elevations for the 10-, 50-, 100-, and 500-year floods, as determined at each cross section, may be found in Table 1 "Flood Frequency-Elevation and Discharge Data". Figures, 1 through 5, show a graphical representation of high water elevations at typical valley cross sections. Water surface elevations computed at each cross section were used to prepare flood profiles, sheets 1 through 23, which show the streambed elevation in relation to water surface elevations for the 10-, 50-, 100-, and 500-year frequency floods.

The flood profiles may be used in areas where controversy arises over the 100-year flood boundary shown on the Flood Plain Maps. Since the flood profile exhibits give the water surface elevation at a specific

point on the reference line, the flood elevations can be surveyed on the ground to alleviate any discrepancies on the base map.

### C. Flooded Areas

Included flood plain maps show the boundary of the 100-year flood plain. Normally the 500-year frequency flood plain is also shown on these maps; however, shallow flow depths and the steep sloping tributaries involved in this study make it impossible in most locations to differentiate between the two frequencies on the scale of maps published in this report. The flood plain boundary was plotted from the flood profiles by determining channel stationing of flood contours at the same interval as the topographic maps. Flood contours, shown as wiggly lines, extend perpendicular to the direction of flow and intersect the ground at the edge of the flood plain.

The area included within the 100-year flood line boundry is about 370 acres for the 5 tributaries.

## Hydrology

The basin characteristics suggest that summer rainfall events would pose the greatest threat to severe flooding in Silt. Snowmelt flooding is more likely to cause minor flooding. There was insufficient streamflow data of rainfall flood events to analyse, therefore the SCS TR-20 computer program was used to simulate rainfall flood peaks. The TR-20 analysis included the standard SCS Type II (24 hour) rainfall distribution and curve numbers for an average antecedent soil moisture condition (AMC-II).

The model was run for individual basins; however, adjustments were made at locations where split flow occurred or where flows combined. The discharge-frequency values from the model were reviewed to ensure the data was reasonable and then used as input to HEC-2 in the hydraulic analysis.

See the table of expected flood discharges in the flood history section for further information.



## Hydraulics

The U.S. Army Engineers HEC-2 computer program was used to perform water surface profile computations. Numerous bridges and culverts exist along the channels through the study reach. Dimensions for these road crossings were determined from field investigations and the data was integrated into appropriate cross section data.

Cross section data, and reach length information were obtained from 2 foot contour topographic maps. Maps were prepared especially for this study, at a scale of 1 inch = 200 ft. with 2.0 ft contour intervals.

Hydraulic roughness coefficients (Mannings N-Values) were determined from field investigations and documented with photographs (in technical addendum). A tabulation of roughness coefficients is included in the technical addendum.

Water surface profiles, typical cross sections and maps showing the 100-year flood boundaries are shown on included exhibits and flood plain maps. Table 1 shows computed flood elevations at specific cross sections.

Flood lines were located on the maps by transferring flood elevations (at map contour intervals) from plotted profiles (from HEC-2) to the maps, using stationing along the main channel as the location reference. These points were connected and smoothed to create the map flood lines.

The Lower Cactus Valley Ditch, which passes through the Town of Silt, is a significant factor in the study. The ditch is near capacity during the summer months and therefore can contribute little in its present condition towards intercepting local runoff. Field surveys and water surface profile analyses show the carrying capacity of the ditch to be about 35-40 cfs (irrigation rights are for 50 cfs). The necessary hydraulic studies for possible enlargement of the ditch, as a part of an alternative treatment plan, were made and conclusions shown in the "Structural Flood Control Measures" section of this report.

## FLOOD PLAIN MANAGEMENT

Potential flood damages to existing development and possible loss of life can be alleviated or lessened through non-structural and structural flood hazard mitigation methods.

Non-structural methods include: local flood plain regulations, land treatment, flood warning and forecasting systems, flood insurance, flood proofing, flood fighting and emergency evacuations.

### Local Regulations

The need to minimize property damage due to flooding has been recognized by planners and local community officials. Subdividers and developers are required to submit proposed storm drainage plans to the planning commission for approval. In the past, drainage plans have been prepared singularly or on a plat-by-plat basis. Information contained in this report will be useful in developing a master drainage plan for the study area. This report provides the outline of flood hazard areas on large scale maps specifically for this purpose.

The city may provide zoning regulations...

..."to establish, regulate, restrict, and limit such uses on or along any storm or floodwater runoff channel or basin, as such storm or floodwater runoff channel or basin has been designated and approved by the Colorado Water Conservation Board, in order to lessen or avoid the hazards to persons and damage to property resulting from the accumulation of storm or floodwaters"...

as stated in Section 30-28-111 for county governments and Sections 31-23-301 for municipal governments of the Colorado Revised Statutes.

### Colorado Natural Hazard Area Regulations

In 1974, the Colorado General Assembly passed House Bill 1041, a bill "concerning land use, and providing for identification, designation, and administration of areas and activities of State interest,..." (H.B. 1041, Title 24, Article 65.1, CRS, as amended). Areas of State interest include natural hazard areas, or those areas that are "so adverse to past, current, or foreseeable construction or land use as to constitute a significant hazard to public health and safety or to property." Flood plains are natural hazard areas.

With reference to the administration of natural hazard areas, section 24-65.1-202(2)(a) of the Act provides: Flood plains shall be administered so as to minimize significant hazard to public health and safety or to property; open space activities shall be encouraged; structures shall be designed in terms of use and hazards; disposal sites and systems shall be protected from inundation by floodwaters; and activities shall be discouraged which, in time of flooding, would create significant hazards to public health and safety or to property.

The Act further provides that after promulgation of guidelines for land use in natural hazard areas..., the natural hazard areas shall be administered by local government in a manner which is consistent with the guidelines for land use in each of the natural hazard areas.

### Colorado Water Conservation Board Designation

Concerning the designation of the flood plain, the Colorado Water Conservation Board is charged with the primary responsibility for:

1. Making recommendations to local governments and the Colorado Land Use Commission.
2. Providing technical assistance to local governments.

The Board's power and duty is ...

..."to devise and formulate methods, means and plans for bringing about the greater utilization of the waters of the state and prevention of flood damages therefrom, and to designate and approve storm or floodwater runoff channels or basins, and to make such designations available to legislative bodies of cities and incorporated towns, to county planning commissions, and to boards of adjustment of cities, incorporated towns, and counties of this state"...

as stated in Section 37-60-106 (1) (c) of the Colorado Revised Statutes

Upon review and approval of this report, the Colorado Water Conservation Board will designate and approve as flood plain areas those areas inundated by the 100-year flood as described by the floodwater surface elevations and profiles in this report. The use of the designated flood plain areas may then be regulated by the local government.

#### Model Regulations

Model flood plain regulations have been promulgated by the Colorado Water Conservation Board, with the purpose to promote public health, safety, and general welfare, and minimize flood hazards and losses. The model includes provisions designed to:

1. Promote sound planning and land use, and permit only such uses within flood plains that will not endanger life, health, and public safety or property in times of flooding.
2. Protect the public from avoidable financial expenditures for flood control projects, flood relief measures, and the repair and restoration of damaged public facilities.
3. Prevent avoidable interruption of business and commerce;
4. Minimize victimization of unwary home and land purchasers; and



5. Facilitate the administration of flood hazard areas by establishing requirements that must be met before use or development is permitted.

The Board's model flood plain regulations offer two options for management of the 100-year flood plain. These are the Hazard Area Concept and the Floodway Concept.

The Hazard Area concept defines the areas of the flood plain in which waters of the 100-year flood attain a maximum depth greater than one and one-half feet as a high hazard area , and a depth less than this as a low hazard area. The Board recommends that no basements should be allowed for structures located within the low hazard area and all habitable living quarters (first floors) should be constructed a minimum of one foot above the 100-year floodwater surface elevations. Development is prohibited in high hazard areas.

The Floodway concept, used in this study, defines the channel of a stream and adjacent flood plain areas that must be kept free of development in order to safely pass the 100-year flood with a minimal rise in the water surface elevation. The rise must be no more than one foot to meet Federal Insurance Administration standards.

## Flood Insurance

The National Flood Insurance Act of 1968 (Title XIII of the Housing and Urban development Act, P.L. 90-448) recognized the necessity for flood plain management. This Act makes federally subsidized insurance available to citizens in communities that adopt regulations controlling future developments of their flood plain. In respect to encroachment on the flood plain, the regulations require:

- (1) New residential construction or substantial improvement of existing homes must have the lowest floor level above the elevation of the 100-year flood.
- (2) Non-residential construction must meet the same standard or be flood proofed to that level.

The 1968 Act benefits owners of structures already in the flood-prone areas by providing insurance coverage that had been unavailable through private companies. The Act created a cooperative program of insurance against flood damage by the private flood insurance industry and the federal government.

The amount of coverage available and the premium rate varies considerably depending on property location within the flood plain and the property value. All property owners shown in this study to be within areas subject to flooding should consider the purchase of flood insurance.

Additional information on the flood Insurance Program is available from local insurance agents or brokers and the:

Federal Emergency Management Agency, Region VIII  
Natural and Technological Hazard Division  
Building 710  
Denver Federal Center  
Denver, Colorado 80225

Telephone 235-4830

The National Flood Insurance Program uses the floodway concept in its rate studies for communities participating in the regular phase of the programs.

#### Flood Warning and Flood Forecasting Systems

The National Oceanic and Atmospheric Administration (NOAA) through its' National Weather Service (NWS), maintains year-around surveillance of weather and flood conditions. Daily weather forecasts are issued through the NWS and disseminated by radio and television stations. A general alert to the danger of flash flooding is one of the services provided by the National Weather Service.

#### Evacuation Plan

An "Emergency Evacuation and Operations Plan" would provide for alerting the public of potential flooding, and coordinating community and county services during an emergency. Plan implementation during the time of an emergency requires cooperation of the general public as well as local officials. This is especially important for flood fighting, evacuation, and rescue operations. Communication is extremely important during flood alerts. Warnings issued through the National Weather Service are disseminated by radio to state and local officials.

## Structural Flood Control Measures

This study is somewhat unique for a flood plain management study because of the planning alternatives included. The future without project flooding situation was considered and used in conjunction with 4 alternative treatment plans to analyze project benefits and economic feasibility. Most USDA programs require an alternative treatment plan to be economically feasible in order to qualify for federal funding. Other sources of financing may not require this; therefore, the alternative treatment plans are included herein, whether or not the plan was found economically feasible.

### Future Without Project Condition

If no structural flood control improvements were applied within the study area, flooding in the future should continue very similar to what has happened in the past. The extent of flood damages to be expected is shown in the following table:

POTENTIAL FLOOD DAMAGES

---

<u>TYPE OF DAMAGE</u> <sup>1/</sup>	<u>Unit</u>	<u>Number</u>	
Residences Flooded	#	58	
Businesses Flooded	#	9	(in addition, 1 school and the county equipment yard)
Streets Flooded	ft.	4,000	
Culverts-Bridges Damaged	#	22	
I-70 Flooded	ft.	3,000	
Railroad Flooded	ft.	850	
County and Private Roads Flooded	ft.	3,200	

---

<sup>1/</sup> (For 100-year frequency)



The above list of damages have been converted into dollars and used in analyzing benefits for the following alternative treatment plans. (See Structural Measures and Comparison of Alternatives tables).

#### Alternative No. 1

This alternative considers; (1) collecting runoff from the East Basin drainage above Lower Cactus Valley Ditch and using a drop inlet spillway to pass this floodwater under the ditch to a stable outlet downstream, (2) diverting Sixteenth Street Basin flows to the east boundary of Silt to a collection area and using a drop inlet spillway to pass this water under Grand Avenue, under the Lower Cactus Valley Ditch, and under US Highway 6 to a location where the flows can be outletted to a stable grade, (3) collecting Seventh Street Basin flows at the mouth of the canyon north of town and using a drop inlet spillway and pipe to carry the flows to the Lower Cactus Valley Ditch where it will outlet into the ditch, (4) building up First Street and County Road 231 to divert First Street Basin flows that exceed culvert and channel capacities to an overflow channel. This overflow channel leads to an adjacent drainage to the west. The overflow would be collected at the Lower Cactus Valley Ditch into a drop inlet spillway that would pass under the ditch and continue to an area below the small pond at City Park near Dogwood Drive, (5) lining the Lower Cactus Valley Ditch from Seventh Street to the channel west of town that leads to the City Park referred to in Item 4 above. The lined ditch would handle flood flows from Seventh Street Basin as well as irrigation flows. Ditch flows greater than 50 cfs would be spilled into the City Park drainage because of the limited capacity of an inverted siphon structure a short distance downstream.

This alternative would include no improvements on the West Basin because there appears to be no significant flood damages along this channel.

#### Alternative No. 2

This alternative would be the same as Alternative No. 1 with the following exceptions:

1. Item number 3 would include a continuation of the pipe under the Lower Cactus Valley Ditch and on south to the railroad. A pipe would be jacked under the railroad to allow discharge at a stable outlet above I-70.
2. Item number 5 (ditch lining) would not be included.

#### Alternative No. 3

This alternative would include lining the Lower Cactus Valley Ditch from Ninth Street to a spill location at the City Park Drainage. The capacity of the lined ditch would be sufficient to carry flood flows from Seventh Street Basin and normal irrigation flows (50 cfs). Some dike work would also be necessary at County Road 231 on First Street Basin similar to Item No. 4 in Alternative No. 1. There would be no improvements to West Basin, Sixteenth Street Basin, or East Basin in this alternative.

#### Alternative No. 4

This alternative will involve cleaning and enlargement of the Lower Cactus Valley Ditch from Ninth Street to a spill location at the City Park Drainage. The capacity of the enlarged ditch would be sufficient to carry flood flows from Seventh Street Basin and normal irrigation flows (50 cfs). Some dike work would also be necessary at County Road 231 on First Street Basin similar to item 4 in Alternative No. 1. Regular maintenance would be important with this alternative. There would be no improvements to West Basin, Sixteenth Street Basin, or East Basin.

The following tables show structural measures, estimated construction costs, and benefits for each of the above alternatives.

STRUCTURAL MEASURES					
Work Item	Unit	Alt 1	Alt 2	Alt 3	Alt 4
Concrete Drop Inlet Str	Number	4	4	1	1
Concrete Ditch Lining	Feet	3850	---	4870	---
Pipeline	Feet	2400	3430	---	---
Ditch Cleaning & Enlarg.	Feet	1380	1380	1380	6250
Earth Dike	Cu. Yd.	11,700	12,200	---	---

#### COMPARISON OF ALTERNATIVES <sup>1/</sup>

Alternative Cost Comparison	Alt #1	Alt #2	Alt #3	Alt #4
Construction Cost	\$ 962,000	\$ 783,900	\$ 613,800	\$ 209,900
Land Rights Cost	227,200	167,200	99,000	99,000
Eng. & Adm. Asst.	298,200	243,000	190,300	65,000
Total Inst. Cost	<u>\$1,487,400</u>	<u>\$1,194,100</u>	<u>\$ 903,100</u>	<u>\$ 373,900</u>
Annual Alternative Cost and Effects Comparison	Alt #1	Alt #2	Alt #3	Alt #4
Annualized Cost	\$ 154,700	\$ 124,300	\$ 94,100	\$ 39,500
Annualized Benefits	13,500	9,400	11,200	7,100
Net Annualized Benefits	<u>\$ -141,200</u>	<u>\$ -114,900</u>	<u>\$ - 82,900</u>	<u>\$ - 32,400</u>

<sup>1/</sup> Price base September 1986, Discounted and annualized at 8 7/8% for 25 years.

## RECOMMENDATIONS

The following recommendations are included for consideration in reducing potential flood damages.

1. Local units of government should implement a flood plain management or flood hazard mitigation plan.
2. Existing restrictions that contribute to overbank flooding should be corrected where possible and when possible.
3. Structural alternatives studied herein do not appear to be economically feasible projects. This is primarily because of the expected shallow depth of flow within the flood plain. Steep slopes through town generally disperse flood waters except in a few locations. The most cost effective alternative studied is Alternative No. 4 discussed under "Structural Flood Control Measures". This set of treatment measures should be considered in more detail.
4. Owners and occupants of buildings and other property within or adjacent to the delineated flood boundary should consider flood insurance.
5. Public information and education programs on flood hazards should be made available to the public.
6. Native habitat along the main channels should be maintained to preserve channel stability and provide wildlife habitat.

## GLOSSARY OF TERMS

Channel - A natural or artificial water course of perceptible extent with definite banks to confine and conduct continuously or periodically flowing water. Channel flow is that water which is flowing within the limits of the defined channel.

Flood - Water from a river, stream, water course, lake or other body of standing water, that temporarily overflows the boundaries within which it is ordinarily confined.

Flood Crest - The maximum stage or elevation reached by the waters of a flood at a given location.

Flood Frequency - A means of expressing the probability of flood occurrences as determined from statistical analysis of representative streamflow or rainfall and runoff records. The frequency of a particular stage or discharge is usually expressed as occurring once in a specified number of years. The 10-, 50-, 100- and 500-year frequency floods have an average frequency of occurrence in the order of once in the number of years as indicated.

10-Year Flood - A flood having an average frequency of occurrence of once in 10 years. It has a 10 percent chance of being equaled or exceeded in any given year.

100-Year Flood - A flood having an average frequency of occurrence of once in 100 years. It has a 1 percent chance of being equaled or exceeded in any given year.

Flood Hazard Areas - Areas susceptible to flood damage.

Flood Peak - The highest stage or discharge attained during a flood event; also referred to as peak stage or peak discharge.



Flood Plain - The relatively flat or lowland area adjoining a river, stream, watercourse, lake, or other body of standing water which has been or may be covered temporarily by flood water. For administrative purposes the flood plain may be defined as the area that would be inundated by the 100-year flood.

Left Stream Bank - The left bank of the stream when looking downstream.

Perched Channel Flow - A condition where the flow elevation in the outer portions of the flood plain is higher than the flow elevation in the main channel. This condition occurs when a higher secondary channel receives inflow from some location upstream and maintains a flatter slope than the main channel.

Reach - A hydraulic engineering term used to describe longitudinal segments of a stream or river.

Right Stream Bank - The right bank of the stream when looking downstream.

Runoff - That part of precipitation, as well as any other flow contributions, which appears in surface streams of either perennial or intermittent form.

Stream - Any natural channel or depression through which water flows whether continuously, intermittently, or periodically, including modification of the natural channel or depression.

Structure - Anything constructed or erected, the use of which requires a more or less permanent location on or in the ground. Includes but is not limited to bridges, buildings, canals, dams, ditches, diversions, irrigation systems, pumps, pipelines, railroads, roads sewage disposal systems, underground conduits, water supply systems and wells.

Typical Valley Cross Section - An engineering drawing of a vertical section of a stream channel and adjoining landscape as viewed in a

downstream direction. The drawing represents a specified location within a designated stream reach.

Water Surface Profile - (This term is synonymous with Flood Profile) - a graph showing the relationship of the water surface elevation of a flood event to location along a stream or river.


Watersheds - A drainage basin or area which collects runoff and transmits it usually by means of streams and tributaries to the outlet of the basin.

## BIBLIOGRAPHY AND REFERENCES

- Colorado Division of Wildlife - 1978. Essential Habitat for Threatend or Endangered Wildlife in Colorado. Colo. DOW, 84 pp.
- Colorado Water Conservation Board - Graph -100-Year Runoff Ratio vs. Drainage Area, Colorado River Basin in Colorado, April, 1979.
- Colorado Water Conservation Board - Manual for Estimating Flood Characteristics of Natural Flow Streams in Colorado - Technical Manual No. 1, 1976.
- Colorado Water Conservation Board - Manual for Local Governments, Flood Plain Management, Flood Control and Flood Disaster Programs, June 1976.
- Colorado Water Conservation Board, Memorandum - Una Dam and Reservoir Feasibility Study Hydrology, March, 1982.
- Denver Engineering Corporation, Hydrology Report for City of Aspen and Pitkin County (Unincorporated) Flood Insurance Studies, January 1984.
- Morrison-Knudsen Co. Ins., Clear Creek Shale Oil Project, Planning Study No. 67, July 1981.
- Simons, Li & Associates, Inc., Hydrology Report For Town of Rangley, City of Rifle and Garfield County Flood Insurance Studies, January 1983.
- U.S. Department of Agriculture, Soil Conservation Service - Flood Plain Management and Wetlands Protection, Implementation of Executive Orders 11988 and 11990, Federal Register, Vol. 43, No. 107, June 2, 1978.
- U.S. Department of Agriculture, Soil Conservation Service - Guide for Selecting Roughness Coefficients "N" Values for Channels, December 1963.
- U.S. Department of the Army, Corps of Engineers, Flood Insurance Study Hydrology, Garfield and Mesa Counties, November 1975.
- U.S. Department of the Army, Corps of Engineers, Flood Plain Information, Colorado River and Rifle, Government, and Hubbard Gulch Creeks, Rifle Colorado, April 1973.
- U.S. Department of the Army, Corps of Engineers, HEC-2 Water Surface Profile, January 1981.
- U.S. Department of the Army, Office of the Chief of Engineers - A Perspective on Flood Plain Regulations for Flood Plain Management, EP 1165-2-304, June 1976.



- U.S. Department of Housing and Urban Development, Federal Insurance Administration - Elevated Residential Structures, Reducing Flood Damage Through Building Design, HUD-FIA-184, Guide Manual, September 1976.
- U.S. Department of Housing and Urban Development, Federal Insurance Administration - National Flood Insurance Program, Federal Register, Vol. 41, No. 207, October 26, 1976.
- U.S. Department of the Interior, Geological Survey - Water Supply Paper 997, Floods in Colorado, by Robert Follansbee and Leon R. Sawyer, 1948.
- U.S. Department of the Interior - Water Supply Paper 1681, Magnitude and Frequency of Floods in the U.S., Part 7.
- U.S. Water Resources Council - Regulation of Flood Hazard Areas to Reduce Flood Losses, Volume One and Two, 1971 and 1972.
- Federal Emergency Management Agency - A Unified National Program for Flood Plain Management, March 1986.



FLOOD PLAIN INDEX MAP  
TOWN OF SILT  
FLOOD PLAIN MANAGEMENT STUDY






LEGEND  
FLOOD PLAIN LIMITS

- 100 YEAR FLOOD
- GROUND ELEVATION IN FEET MEAN SEA LEVEL DATUM
- CONTOUR INTERVAL 2.0'
- CROSS SECTION
- CROSS SECTION CONTINUED
- INTERMITTENT STREAM
- HORIZONTAL CONTROL
- VERTICAL CONTROL
- PHOTO CENTER
- GRID POINT
- 100 YEAR FLOOD ELEV. 5280

C-69 INDEX NUMBER FOR COLORADO RIVER MAPPING PROJECT SHEETS 1,6 AND PARTS OF 2,7,10,11  
TOPOGRAPHY COMPILED BY PHOTOGRAMMETRIC METHODS FROM 6" C.F.L. VERTICAL AERIAL PHOTOGRAPHY TAKEN NOV. 15, 16 & 17, 1982. BASIS OF HORIZONTAL CONTROL: THE COLORADO STATE PLANE COORDINATE SYSTEM, CENTRAL ZONE, LAMBERT CONFORMAL CONIC PROJECTION. THE FOLLOWING (USC & GS AND /OR USGS) TRIANGULATION STATIONS WERE USED: CATHERINE COORDINATES X=1,516,508.42 Y=581,255.78. GNAT-X=1,231,566.60 Y=523,643.10. BASIS OF VERTICAL CONTROL: USC & GS SEA LEVEL DATUM BASED ON THE FOLLOWING BENCHMARKS: O-156 ELEVATION 6192.284. 4870.74PS-ELEVATION 4869.860. PREPARED BY ANALYTICAL SURVEYS, INC. 4167 SINTON ROAD, COLORADO SPRINGS, CO. 80907.

SHEETS 3,4,5,8,9,12,13,14 AND PARTS OF 2,7,10,11  
COORDINATE SYSTEM IS THE MODIFIED COLORADO STATE PLANE COORDINATE SYSTEM, CENTRAL ZONE, LAMBERT CONFORMAL CONIC PROJECTION. THE FOLLOWING (USC & GS AND USGS) TRIANGULATION STATIONS WERE USED: GRAY HOLLOW X=1,395,770.68, Y=613,053.61, CASTLE X=1,432,094.81, Y=623,300.73, ANTLER X=1,371,760.95, Y=630,478.31. BASIS OF VERTICAL CONTROL: USC & GS AND USGS. SEA LEVEL DATUM BASED ON THE FOLLOWING BENCHMARKS: RIFLE ELEV. 5319.199, NEW CASTLE ELEV. 5747.82. TOPOGRAPHY COMPILED BY PHOTOGRAMMETRIC METHODS FROM 6" C.F.L. VERTICAL AERIAL PHOTOGRAPHY TAKEN JAN. 12, 1983. COMPILED BY BELL MAPPING CO., 500 KALAMATH ST. DENVER CO.



REVISION	DATE	BY

U. S. DEPARTMENT OF AGRICULTURE  
SOIL CONSERVATION SERVICE

FLOOD PLAINS  
FLOOD PLAIN MANAGEMENT STUDY  
TOWN OF SILT  
IN GARFIELD COUNTY  
COLORADO

200 0 200 400 600  
SCALE IN FEET


SHEET 1 OF 14








# LEGEND FLOOD PLAIN LIMITS



C-69 INDEX NUMBER FOR COLORADO RIVER MAPPING PROJECT  
SHEETS 1,6 AND PARTS OF 2,7,10,11  
TOPOGRAPHY COMPILED BY PHOTOGRAMMETRIC METHODS FROM  
6" C.F.L. VERTICAL AERIAL PHOTOGRAPHY TAKEN NOV.15,16 & 17,  
1982. BASIS OF HORIZONTAL CONTROL: THE COLORADO STATE  
PLANE COORDINATE SYSTEM, CENTRAL ZONE, LAMBERT  
CONFORMAL CONIC PROJECTION. THE FOLLOWING (USC & GS AND  
/OR USGS) TRIANGULATION STATIONS WERE USED: CATHERINE  
COORDINATES X=1,516,508.42 Y=581,255.78. GNAT-X=1,231,566.60  
Y=523,643.10. BASIS OF VERTICAL CONTROL: USC & GS SEA LEVEL  
DATUM BASED ON THE FOLLOWING BENCHMARKS: D-156 ELEVATION  
6192.284. 4870.74PS-ELEVATION 4869.860. PREPARED BY ANALYTICAL  
SURVEYS, INC. 4167 SINTON ROAD, COLORADO SPRINGS, CO. 80907.

SHEETS 3,4,5,8,9,12,13,14 AND PARTS OF 2,7,10,11  
COORDINATE SYSTEM IS THE MODIFIED COLORADO STATE PLANE  
COORDINATE SYSTEM, CENTRAL ZONE, LAMBERT CONFORMAL  
CONIC PROJECTION. THE FOLLOWING (USC & GS AND USGS)  
TRIANGULATION STATIONS WERE USED: GRAY HOLLOW X=1,395,770.68,  
Y=613,033.61, CASTLE X=1,432,094.81, Y=623,300.73, ANTLER  
X=1,371,760.95, Y=630,478.31. BASIS OF VERTICAL CONTROL:  
USC & GS AND USGS. SEA LEVEL DATUM BASED ON THE FOLLOWING  
BENCHMARKS: RIFLE ELEV. 5319.199, NEW CASTLE ELEV. 5747.82.  
TOPOGRAPHY COMPILED BY PHOTOGRAMMETRIC METHODS FROM  
6" C.F.L. VERTICAL AERIAL PHOTOGRAPHY TAKEN JAN. 12, 1983.  
COMPILED BY BELL MAPPING CO., 500 KALAMATH ST. DENVER CO.




REVISION	DATE	BY

U. S. DEPARTMENT OF AGRICULTURE  
SOIL CONSERVATION SERVICE

FLOOD PLAINS  
FLOOD PLAIN MANAGEMENT STUDY  
TOWN OF SILT  
IN GARFIELD COUNTY  
COLORADO




SHEET 2 OF 14













LEGEND  
FLOOD PLAIN LIMITS



C-69 INDEX NUMBER FOR COLORADO RIVER MAPPING PROJECT  
SHEETS 1, 6 AND PARTS OF 2, 7, 10, 11  
TOPOGRAPHY COMPILED BY PHOTOGRAMMETRIC METHODS FROM  
6" C.F.L. VERTICAL AERIAL PHOTOGRAPHY TAKEN NOV. 15, 16 & 17,  
1982. BASIS OF HORIZONTAL CONTROL: THE COLORADO STATE  
PLANE COORDINATE SYSTEM, CENTRAL ZONE, LAMBERT  
CONFORMAL CONIC PROJECTION. THE FOLLOWING (USC & GS AND  
/OR USGS) TRIANGULATION STATIONS WERE USED: CATHERINE  
COORDINATES X=1,516,508.42 Y=581,255.78. GNAT-X=1,231,566.60  
Y=523,643.10. BASIS OF VERTICAL CONTROL: USC & GS SEA LEVEL  
DATUM BASED ON THE FOLLOWING BENCHMARKS: O-156 ELEVATION  
6192.284, 4870.74PS-ELEVATION 4869.860. PREPARED BY ANALYTICAL  
SURVEYS, INC. 4167 SINTON ROAD, COLORADO SPRINGS, CO. 80907.

SHEETS 3, 4, 5, 8, 9, 12, 13, 14 AND PARTS OF 2, 7, 10, 11  
COORDINATE SYSTEM IS THE MODIFIED COLORADO STATE PLANE  
COORDINATE SYSTEM, CENTRAL ZONE, LAMBERT CONFORMAL  
CONIC PROJECTION. THE FOLLOWING (USC & GS AND USGS)  
TRIANGULATION STATIONS WERE USED: DRY HOLLOW X=1,395,770.68,  
Y=613,033.61, CASTLE X=1,432,094.81, Y=623,300.73, ANTLER  
X=1,371,760.95, Y=630,478.31. BASIS OF VERTICAL CONTROL:  
USC & GS AND USGS SEA LEVEL DATUM BASED ON THE FOLLOWING  
BENCHMARKS: RIFLE ELEV. 5319.199, NEW CASTLE ELEV. 5747.82.  
TOPOGRAPHY COMPILED BY PHOTOGRAMMETRIC METHODS FROM  
6" C.F.L. VERTICAL AERIAL PHOTOGRAPHY TAKEN JAN. 12, 1983.  
COMPILED BY BELL MAPPING CO., 500 KALAMATH ST. DENVER CO.



REVISION	DATE	BY

U. S. DEPARTMENT OF AGRICULTURE  
SOIL CONSERVATION SERVICE

FLOOD PLAINS  
FLOOD PLAIN MANAGEMENT STUDY  
TOWN OF SILT  
IN GARFIELD COUNTY  
COLORADO


200 0 200 400 600  
SCALE IN FEET

SHEET 3 OF 14










# LEGEND FLOOD PLAIN LIMITS

- 100 YEAR FLOOD
- GROUND ELEVATION IN FEET  
MEAN SEA LEVEL DATUM
- CONTOUR INTERVAL 2.0'
- CROSS SECTION
- CROSS SECTION CONTINUED
- INTERMITTENT STREAM
- HORIZONTAL CONTROL
- VERTICAL CONTROL
- PHOTO CENTER
- GRID POINT
- 100 YEAR FLOOD ELEV.

C-69 INDEX NUMBER FOR COLORADO RIVER MAPPING PROJECT  
SHEETS 1,6 AND PARTS OF 2,7,10,11  
TOPOGRAPHY COMPILED BY PHOTOGRAMMETRIC METHODS FROM  
6" C.F.L. VERTICAL AERIAL PHOTOGRAPHY TAKEN NOV. 15, 16 & 17,  
1982. BASIS OF HORIZONTAL CONTROL: THE COLORADO STATE  
PLANE COORDINATE SYSTEM, CENTRAL ZONE, LAMBERT  
CONFORMAL CONIC PROJECTION. THE FOLLOWING (USC & GS AND  
/OR USGS) TRIANGULATION STATIONS WERE USED: CATHERINE  
COORDINATES X=1,516,508.42 Y=581,255.78. GNAT-X=1,231,566.60  
Y=523,643.10. BASIS OF VERTICAL CONTROL: USC & GS SEA LEVEL  
DATUM BASED ON THE FOLLOWING BENCHMARKS: 0-156 ELEVATION  
6192.284. 4870.74PS-ELEVATION 4869.860. PREPARED BY ANALYTICAL  
SURVEYS, INC. 4167 SINTON ROAD, COLORADO SPRINGS, CO. 80907.

SHEETS 3,4,5,8,9,12,13,14 AND PARTS OF 2,7,10,11  
COORDINATE SYSTEM IS THE MODIFIED COLORADO STATE PLANE  
COORDINATE SYSTEM, CENTRAL ZONE, LAMBERT CONFORMAL  
CONIC PROJECTION. THE FOLLOWING (USC & GS AND USGS)  
TRIANGULATION STATIONS WERE USED: ORY HOLLOW X=1,395,770.68,  
Y=613,033.61. CASTLE X=1,432,094.81, Y=623,300.73. ANTLER  
X=1,371,760.95, Y=630,478.31. BASIS OF VERTICAL CONTROL:  
USC & GS AND USGS. SEA LEVEL DATUM BASED ON THE FOLLOWING  
BENCHMARKS: RIFLE ELEV. 5319.199, NEW CASTLE ELEV. 5747.82.  
TOPOGRAPHY COMPILED BY PHOTOGRAMMETRIC METHODS FROM  
6" C.F.L. VERTICAL AERIAL PHOTOGRAPHY TAKEN JAN. 12, 1983.  
COMPILED BY BELL MAPPING CO., 500 KALAMATH ST. DENVER CO.



REVISION	DATE	BY

**U. S. DEPARTMENT OF AGRICULTURE  
SOIL CONSERVATION SERVICE**

**FLOOD PLAINS  
FLOOD PLAIN MANAGEMENT STUDY  
TOWN OF SILT  
IN GARFIELD COUNTY  
COLORADO**

200 0 200 400 600  
SCALE IN FEET


**SHEET 4 OF 14**








LEGEND  
FLOOD PLAIN LIMITS



C-69 INDEX NUMBER FOR COLORADO RIVER MAPPING PROJECT  
SHEETS 1,6 AND PARTS OF 2,7,10,11  
TOPOGRAPHY COMPILED BY PHOTOGRAMMETRIC METHODS FROM  
6" C.F.L. VERTICAL AERIAL PHOTOGRAPHY TAKEN NOV.15,16 & 17,  
1982. BASIS OF HORIZONTAL CONTROL: THE COLORADO STATE  
PLANE COORDINATE SYSTEM, CENTRAL ZONE, LAMBERT  
CONFORMAL CONIC PROJECTION. THE FOLLOWING (USC & GS AND  
/OR USGS) TRIANGULATION STATIONS WERE USED: CATHERINE  
COORDINATES X=1,516,508.42 Y=581,255.78. GNAT-X=1,231,566.60  
Y=523,643.10. BASIS OF VERTICAL CONTROL: USC & GS SEA LEVEL  
DATUM BASED ON THE FOLLOWING BENCHMARKS: O-156 ELEVATION  
6192.284. 4870.74PS-ELEVATION 4869.860. PREPARED BY ANALYTICAL  
SURVEYS, INC. 4167 SINTON ROAD, COLORADO SPRINGS, CO. 80907.

SHEETS 3,4,5,8,9,12,13,14 AND PARTS OF 2,7,10,11  
COORDINATE SYSTEM IS THE MODIFIED COLORADO STATE PLANE  
COORDINATE SYSTEM, CENTRAL ZONE, LAMBERT CONFORMAL  
CONIC PROJECTION. THE FOLLOWING (USC & GS AND USGS)  
TRIANGULATION STATIONS WERE USED: ORY HOLLOW X=1,395,770.68,  
Y=613,053.61, CASTLE X=1,432,094.81, Y=623,300.73, ANTLER  
X=1,371,760.95, Y=630,478.31. BASIS OF VERTICAL CONTROL:  
USC & GS AND USGS. SEA LEVEL DATUM BASED ON THE FOLLOWING  
BENCHMARKS: RIFLE ELEV. 5319.199, NEW CASTLE ELEV. 5747.82.  
TOPOGRAPHY COMPILED BY PHOTOGRAMMETRIC METHODS FROM  
6" C.F.L. VERTICAL AERIAL PHOTOGRAPHY TAKEN JAN.12, 1983.  
COMPILED BY BELL MAPPING CO., 500 KALAMATH ST. DENVER CO.



REVISION DATE BY

U. S. DEPARTMENT OF AGRICULTURE  
SOIL CONSERVATION SERVICE

FLOOD PLAINS  
FLOOD PLAIN MANAGEMENT STUDY  
TOWN OF SILT  
IN GARFIELD COUNTY  
COLORADO


200 0 200 400 600  
SCALE IN FEET

SHEET 5 OF 14










LEGEND  
FLOOD PLAIN LIMITS

- 100 YEAR FLOOD
- GROUND ELEVATION IN FEET  
MEAN SEA LEVEL DATUM
- CONTOUR INTERVAL 2.0'
- CROSS SECTION
- CROSS SECTION CONTINUED
- INTERMITTENT STREAM
- HORIZONTAL CONTROL
- VERTICAL CONTROL
- PHOTO CENTER
- GRID POINT
- 100 YEAR FLOOD ELEV.

C-69 INDEX NUMBER FOR COLORADO RIVER MAPPING PROJECT  
SHEETS 1,6 AND PARTS OF 2,7,10,11  
TOPOGRAPHY COMPILED BY PHOTOGRAMMETRIC METHODS FROM  
6" C.F.L. VERTICAL AERIAL PHOTOGRAPHY TAKEN NOV. 15, 16 & 17,  
1982. BASIS OF HORIZONTAL CONTROL: THE COLORADO STATE  
PLANE COORDINATE SYSTEM, CENTRAL ZONE, LAMBERT  
CONFORMAL CONIC PROJECTION. THE FOLLOWING (USC & GS AND  
/OR USGS) TRIANGULATION STATIONS WERE USED: CATHERINE  
COORDINATES X=1,516,508.42 Y=561,255.78. GNAT-X=1,231,566.60  
Y=523,643.10. BASIS OF VERTICAL CONTROL: USC & GS SEA LEVEL  
DATUM BASED ON THE FOLLOWING BENCHMARKS: 0-156 ELEVATION  
6192.284, 4870.74PS-ELEVATION 4869.860. PREPARED BY ANALYTICAL  
SURVEYS, INC. 4167 SINTON ROAD, COLORADO SPRINGS, CO. 80907.  
SHEETS 3,4,5,8,9,12,13,14 AND PARTS OF 2,7,10,11  
COORDINATE SYSTEM IS THE MODIFIED COLORADO STATE PLANE  
COORDINATE SYSTEM, CENTRAL ZONE, LAMBERT CONFORMAL  
CONIC PROJECTION. THE FOLLOWING (USC & GS AND USGS)  
TRIANGULATION STATIONS WERE USED: GRAY HOLLOW X=1,395,770.69,  
Y=613,033.61, CASTLE X=1,432,094.81, Y=623,300.73, ANTLER  
X=1,371,760.95, Y=630,478.31. BASIS OF VERTICAL CONTROL:  
USC & GS AND USGS. SEA LEVEL DATUM BASED ON THE FOLLOWING  
BENCHMARKS: RIFLE ELEV. 5319.199, NEW CASTLE ELEV. 5747.82.  
TOPOGRAPHY COMPILED BY PHOTOGRAMMETRIC METHODS FROM  
6" C.F.L. VERTICAL AERIAL PHOTOGRAPHY TAKEN JAN. 12, 1983.  
COMPILED BY BELL MAPPING CO., 500 KALAMATH ST. DENVER CO.



REVISION	DATE	BY

U. S. DEPARTMENT OF AGRICULTURE  
SOIL CONSERVATION SERVICE

FLOOD PLAINS  
FLOOD PLAIN MANAGEMENT STUDY  
TOWN OF SILT  
IN GARFIELD COUNTY  
COLORADO


200 0 200 400 600  
SCALE IN FEET

SHEET 6 OF 14










LEGEND  
FLOOD PLAIN LIMITS

- 100 YEAR FLOOD
- GROUND ELEVATION IN FEET MEAN SEA LEVEL DATUM
- CONTOUR INTERVAL 2.0'
- CROSS SECTION
- CROSS SECTION CONTINUED
- INTERMITTENT STREAM
- HORIZONTAL CONTROL
- VERTICAL CONTROL
- PHOTO CENTER
- GRID POINT
- 100 YEAR FLOOD ELEV.

C-69 INDEX NUMBER FOR COLORADO RIVER MAPPING PROJECT  
SHEETS 1,6 AND PARTS OF 2,7,10,11  
TOPOGRAPHY COMPILED BY PHOTOGRAMMETRIC METHODS FROM 6" C.F.L. VERTICAL AERIAL PHOTOGRAPHY TAKEN NOV. 15, 16 & 17, 1982. BASIS OF HORIZONTAL CONTROL: THE COLORADO STATE PLANE COORDINATE SYSTEM, CENTRAL ZONE, LAMBERT CONFORMAL CONIC PROJECTION. THE FOLLOWING (USC & GS AND /OR USGS) TRIANGULATION STATIONS WERE USED: CATHERINE COORDINATES X=1,516,508.42 Y=581,255.78. GNAT-X=1,231,566.60 Y=523,643.10. BASIS OF VERTICAL CONTROL: USC & GS SEA LEVEL DATUM BASED ON THE FOLLOWING BENCHMARKS: D-156 ELEVATION 6192.284. 4870.74PS-ELEVATION 4869.860. PREPARED BY ANALYTICAL SURVEYS, INC. 4167 SINTON ROAD, COLORADO SPRINGS, CO. 80907.

SHEETS 3,4,5,8,9,12,13,14 AND PARTS OF 2,7,10,11  
COORDINATE SYSTEM IS THE MODIFIED COLORADO STATE PLANE COORDINATE SYSTEM, CENTRAL ZONE, LAMBERT CONFORMAL CONIC PROJECTION. THE FOLLOWING (USC & GS AND USGS) TRIANGULATION STATIONS WERE USED: DRY HOLLOW X=1,395,770.68, Y=613,033.61, CASTLE X=1,432,094.81, Y=623,300.73, ANTLER X=1,371,760.96, Y=630,478.31. BASIS OF VERTICAL CONTROL: USC & GS AND USGS. SEA LEVEL DATUM BASED ON THE FOLLOWING BENCHMARKS: RIFLE ELEV. 5319.199, NEW CASTLE ELEV. 5747.82. TOPOGRAPHY COMPILED BY PHOTOGRAMMETRIC METHODS FROM 6" C.F.L. VERTICAL AERIAL PHOTOGRAPHY TAKEN JAN. 12, 1983. COMPILED BY BELL MAPPING CO., 500 KALAMATH ST. DENVER CO.



REVISION	DATE	BY

**U. S. DEPARTMENT OF AGRICULTURE  
SOIL CONSERVATION SERVICE**


**FLOOD PLAINS  
FLOOD PLAIN MANAGEMENT STUDY  
TOWN OF SILT  
IN GARFIELD COUNTY  
COLORADO**

**SHEET 7 OF 14**










**LEGEND  
FLOOD PLAIN LIMITS**

- 100 YEAR FLOOD
- GROUND ELEVATION IN FEET  
MEAN SEA LEVEL DATUM
- CONTOUR INTERVAL 2.0'
- CROSS SECTION
- CROSS SECTION CONTINUED
- INTERMITTENT STREAM
- HORIZONTAL CONTROL
- VERTICAL CONTROL
- PHOTO CENTER
- GRIO POINT
- 100 YEAR FLOOD ELEV.

C-69 INDEX NUMBER FOR COLORADO RIVER MAPPING PROJECT  
SHEETS 1,6 AND PARTS OF 2,7,10,11  
TOPOGRAPHY COMPILED BY PHOTOGRAMMETRIC METHODS FROM  
6" C.F.L. VERTICAL AERIAL PHOTOGRAPHY TAKEN NOV.15,16 & 17,  
1982. BASIS OF HORIZONTAL CONTROL: THE COLORADO STATE  
PLANE COORDINATE SYSTEM, CENTRAL ZONE, LAMBERT  
CONFORMAL CONIC PROJECTION. THE FOLLOWING (USC & GS AND  
/OR USGS) TRIANGULATION STATIONS WERE USED: CATHERINE  
COORDINATES X=1,516,508.42 Y=581,255.78. GNAT-X=1,231,566.60  
Y=523,643.10. BASIS OF VERTICAL CONTROL: USC & GS SEA LEVEL  
DATUM BASED ON THE FOLLOWING BENCHMARKS: 0-156 ELEVATION  
6192.284. 4870.74PS-ELEVATION 4869.860. PREPARED BY ANALYTICAL  
SURVEYS, INC. 4167 SINTON ROAD, COLORADO SPRINGS, CO. 80907.


SHEETS 3,4,5,8,9,12,13,14 AND PARTS OF 2,7,10,11  
COORDINATE SYSTEM IS THE MODIFIED COLORADO STATE PLANE  
COORDINATE SYSTEM, CENTRAL ZONE, LAMBERT CONFORMAL  
CONIC PROJECTION. THE FOLLOWING (USC & GS AND USGS)  
TRIANGULATION STATIONS WERE USED: ORY HOLLOW X=1,395,770.68,  
Y=613,033.61, CASTLE X=1,432,094.81, Y=623,300.73, ANTLER  
X=1,371,760.95, Y=630,478.31. BASIS OF VERTICAL CONTROL:  
USC & GS AND USGS. SEA LEVEL DATUM BASED ON THE FOLLOWING  
BENCHMARKS: RIFLE ELEV. 5319.199, NEW CASTLE ELEV. 5747.82.  
TOPOGRAPHY COMPILED BY PHOTOGRAMMETRIC METHODS FROM  
6" C.F.L. VERTICAL AERIAL PHOTOGRAPHY TAKEN JAN. 12, 1983.  
COMPILED BY BELL MAPPING CO., 500 KALAMATH ST. DENVER CO.



REVISION	DATE	BY
----------	------	----

**U. S. DEPARTMENT OF AGRICULTURE  
SOIL CONSERVATION SERVICE**

**FLOOD PLAINS  
FLOOD PLAIN MANAGEMENT STUDY  
TOWN OF SILT  
IN GARFIELD COUNTY  
COLORADO**











# LEGEND FLOOD PLAIN LIMITS



C-69 INDEX NUMBER FOR COLORADO RIVER MAPPING PROJECT SHEETS 1,6 AND PARTS OF 2,7,10,11 TOPOGRAPHY COMPILED BY PHOTOGRAMMETRIC METHODS FROM 6" C.F.L. VERTICAL AERIAL PHOTOGRAPHY TAKEN NOV. 15, 16 & 17, 1982. BASIS OF HORIZONTAL CONTROL: THE COLORADO STATE PLANE COORDINATE SYSTEM, CENTRAL ZONE, LAMBERT CONFORMAL CONIC PROJECTION. THE FOLLOWING (USC & GS AND/OR USGS) TRIANGULATION STATIONS WERE USED: CATHERINE COORDINATES X=1,516,508.42 Y=581,255.78. GNAT-X=1,231,566.60 Y=523,643.10. BASIS OF VERTICAL CONTROL: USC & GS SEA LEVEL DATUM BASED ON THE FOLLOWING BENCHMARKS: 0-156 ELEVATION 6192.284. 4870.74PS-ELEVATION 4869.860. PREPARED BY ANALYTICAL SURVEYS, INC. 4167 SINTON ROAD, COLORADO SPRINGS, CO. 80907.

SHEETS 3,4,5,8,9,12,13,14 AND PARTS OF 2,7,10,11 COORDINATE SYSTEM IS THE MODIFIED COLORADO STATE PLANE COORDINATE SYSTEM, CENTRAL ZONE, LAMBERT CONFORMAL CONIC PROJECTION. THE FOLLOWING (USC & GS AND/OR USGS) TRIANGULATION STATIONS WERE USED: ORY HOLLOW X=1,395,770.68, Y=613,033.61. CASTLE X=1,432,094.81, Y=623,300.73. ANTLER X=1,371,760.95, Y=630,478.31. BASIS OF VERTICAL CONTROL: USC & GS AND USGS. SEA LEVEL DATUM BASED ON THE FOLLOWING BENCHMARKS: RIFLE ELEV. 5319.199, NEW CASTLE ELEV. 5747.82. TOPOGRAPHY COMPILED BY PHOTOGRAMMETRIC METHODS FROM 6" C.F.L. VERTICAL AERIAL PHOTOGRAPHY TAKEN JAN. 12, 1983. COMPILED BY BELL MAPPING CO., 500 KALAMATH ST. DENVER CO.



REVISION	DATE	BY

**U. S. DEPARTMENT OF AGRICULTURE  
SOIL CONSERVATION SERVICE**

**FLOOD PLAINS  
FLOOD PLAIN MANAGEMENT STUDY  
TOWN OF SILT  
IN GARFIELD COUNTY  
COLORADO**


200 0 200 400 600  
SCALE IN FEET

**SHEET 9 OF 14**










# LEGEND FLOOD PLAIN LIMITS

- 100 YEAR FLOOD
- GROUND ELEVATION IN FEET MEAN SEA LEVEL DATUM
- CONTOUR INTERVAL 2.0'
- CROSS SECTION
- CROSS SECTION CONTINUED
- INTERMITTENT STREAM
- HORIZONTAL CONTROL
- VERTICAL CONTROL
- PHOTO CENTER
- GRIO POINT
- 100 YEAR FLOOD ELEV.

C-69 INDEX NUMBER FOR COLORADO RIVER MAPPING PROJECT  
SHEETS 1,6 AND PARTS OF 2,7,10,11  
TOPOGRAPHY COMPILED BY PHOTOGRAMMETRIC METHODS FROM 6" C.F.L. VERTICAL AERIAL PHOTOGRAPHY TAKEN NOV.15,16 & 17, 1982. BASIS OF HORIZONTAL CONTROL: THE COLORADO STATE PLANE COORDINATE SYSTEM, CENTRAL ZONE, LAMBERT CONFORMAL CONIC PROJECTION. THE FOLLOWING (USC & GS AND /OR USGS) TRIANGULATION STATIONS WERE USED: CATHERINE COORDINATES X=1,516,508.42 Y=581,255.78. GNAT-X=1,231,566.60 Y=523,643.10. BASIS OF VERTICAL CONTROL: USC & GS SEA LEVEL DATUM BASED ON THE FOLLOWING BENCHMARKS: D-156 ELEVATION 6192.284. 4870.74PS-ELEVATION 4869.860. PREPARED BY ANALYTICAL SURVEYS, INC. 4167 SINTON ROAD, COLORADO SPRINGS, CO. 80907.

SHEETS 3,4,5,8,9,12,13,14 AND PARTS OF 2,7,10,11  
COORDINATE SYSTEM IS THE MODIFIED COLORADO STATE PLANE COORDINATE SYSTEM, CENTRAL ZONE, LAMBERT CONFORMAL CONIC PROJECTION. THE FOLLOWING (USC & GS AND USGS) TRIANGULATION STATIONS WERE USED: DRY HOLLOW X=1,395,770.68, Y=613,033.61, CASTLE X=1,432,094.81, Y=623,300.73, ANTLER X=1,371,760.95, Y=630,478.31. BASIS OF VERTICAL CONTROL: USC & GS AND USGS. SEA LEVEL DATUM BASED ON THE FOLLOWING BENCHMARKS: RIFLE ELEV. 5319.199, NEW CASTLE ELEV. 5747.82. TOPOGRAPHY COMPILED BY PHOTOGRAMMETRIC METHODS FROM 6" C.F.L. VERTICAL AERIAL PHOTOGRAPHY TAKEN JAN.12, 1983. COMPILED BY BELL MAPPING CO., 500 KALAMATH ST. DENVER CO.



REVISION	DATE	BY

**U. S. DEPARTMENT OF AGRICULTURE  
SOIL CONSERVATION SERVICE**

**FLOOD PLAINS  
FLOOD PLAIN MANAGEMENT STUDY  
TOWN OF SILT  
IN GARFIELD COUNTY  
COLORADO**

200 0 200 400 600  
SCALE IN FEET

**SHEET 10 OF 14**











# LEGEND FLOOD PLAIN LIMITS



C-69 INDEX NUMBER FOR COLORADO RIVER MAPPING PROJECT  
SHEETS 1,6 AND PARTS OF 2,7,10,11  
TOPOGRAPHY COMPILED BY PHOTOGRAMMETRIC METHODS FROM  
6" C.F.L. VERTICAL AERIAL PHOTOGRAPHY TAKEN NOV. 15, 16 & 17,  
1982. BASIS OF HORIZONTAL CONTROL: THE COLORADO STATE  
PLANE COORDINATE SYSTEM, CENTRAL ZONE, LAMBERT  
CONFORMAL CONIC PROJECTION. THE FOLLOWING (USC & GS AND  
/OR USGS) TRIANGULATION STATIONS WERE USED: CATHERINE  
COORDINATES X=1,516,508.42 Y=581,255.78. GNAT-X=1,231,566.60  
Y=523,643.10. BASIS OF VERTICAL CONTROL: USC & GS SEA LEVEL  
DATUM BASED ON THE FOLLOWING BENCHMARKS: D-156 ELEVATION  
6192.284. 4870.74PS-ELEVATION 4869.860. PREPARED BY ANALYTICAL  
SURVEYS, INC. 4167 SINTON ROAD, COLORADO SPRINGS, CO. 80907.

SHEETS 3,4,5,8,9,12,13,14 AND PARTS OF 2,7,10,11  
COORDINATE SYSTEM IS THE MODIFIED COLORADO STATE PLANE  
COORDINATE SYSTEM, CENTRAL ZONE, LAMBERT CONFORMAL  
CONIC PROJECTION. THE FOLLOWING (USC & GS AND USGS)  
TRIANGULATION STATIONS WERE USED: DRY HOLLOW X=1,395,770.68,  
Y=613,033.61, CASTLE X=1,432,094.81, Y=623,300.73, ANTLER  
X=1,371,760.95, Y=630,478.31. BASIS OF VERTICAL CONTROL:  
USC & GS AND USGS. SEA LEVEL DATUM BASED ON THE FOLLOWING  
BENCHMARKS: RIFLE ELEV. 5319.199, NEW CASTLE ELEV. 5747.82,  
TOPOGRAPHY COMPILED BY PHOTOGRAMMETRIC METHODS FROM  
6" C.F.L. VERTICAL AERIAL PHOTOGRAPHY TAKEN JAN. 12, 1983.  
COMPILED BY BELL MAPPING CO., 500 KALAMATH ST. DENVER CO.



REVISION	DATE	BY

**U. S. DEPARTMENT OF AGRICULTURE  
SOIL CONSERVATION SERVICE**

**FLOOD PLAINS  
FLOOD PLAIN MANAGEMENT STUDY  
TOWN OF SILT  
IN GARFIELD COUNTY  
COLORADO**


200 0 200 400 600  
SCALE IN FEET

**SHEET 11 OF 14**










**LEGEND  
FLOOD PLAIN LIMITS**

- 100 YEAR FLOOD
- GROUND ELEVATION IN FEET MEAN SEA LEVEL DATUM
- CONTOUR INTERVAL 2.0'
- CROSS SECTION
- CROSS SECTION CONTINUED
- INTERMITTENT STREAM
- HORIZONTAL CONTROL
- VERTICAL CONTROL
- PHOTO CENTER
- GRID POINT
- 100 YEAR FLOOD ELEV.

C-69 INDEX NUMBER FOR COLORADO RIVER MAPPING PROJECT  
SHEETS 1,6 AND PARTS OF 2,7,10,11  
TOPOGRAPHY COMPILED BY PHOTOGRAMMETRIC METHODS FROM 6" C.F.L. VERTICAL AERIAL PHOTOGRAPHY TAKEN NOV. 15, 16 & 17, 1982. BASIS OF HORIZONTAL CONTROL: THE COLORADO STATE PLANE COORDINATE SYSTEM, CENTRAL ZONE, LAMBERT CONFORMAL CONIC PROJECTION. THE FOLLOWING (USC & GS AND/OR USGS) TRIANGULATION STATIONS WERE USED: CATHERINE COORDINATES X=1,516,508.42 Y=581,255.78. GNAT-X=1,231,566.60 Y=523,643.10. BASIS OF VERTICAL CONTROL: USC & GS SEA LEVEL DATUM BASED ON THE FOLLOWING BENCHMARKS: 0-156 ELEVATION 6192.284. 4870.74PS-ELEVATION 4869.860. PREPARED BY ANALYTICAL SURVEYS, INC. 4167 SINTON ROAD, COLORADO SPRINGS, CO. 80907.

SHEETS 3,4,5,8,9,12,13,14 AND PARTS OF 2,7,10,11  
COORDINATE SYSTEM IS THE MODIFIED COLORADO STATE PLANE COORDINATE SYSTEM, CENTRAL ZONE, LAMBERT CONFORMAL CONIC PROJECTION. THE FOLLOWING (USC & GS AND USGS) TRIANGULATION STATIONS WERE USED: ORY HOLLOW X=1,395,770.68, Y=613,033.61, CASTLE X=1,432,094.81, Y=623,300.73, ANTLER X=1,371,760.96, Y=630,478.31. BASIS OF VERTICAL CONTROL: USC & GS AND USGS. SEA LEVEL DATUM BASED ON THE FOLLOWING BENCHMARKS: RIFLE ELEV. 5319.199, NEW CASTLE ELEV. 5747.82. TOPOGRAPHY COMPILED BY PHOTOGRAMMETRIC METHODS FROM 6" C.F.L. VERTICAL AERIAL PHOTOGRAPHY TAKEN JAN. 12, 1983. COMPILED BY BELL MAPPING CO., 500 KALAMATH ST. DENVER CO.



REVISION	DATE	BY

**U. S. DEPARTMENT OF AGRICULTURE  
SOIL CONSERVATION SERVICE**

**FLOOD PLAINS  
FLOOD PLAIN MANAGEMENT STUDY  
TOWN OF SILT  
IN GARFIELD COUNTY  
COLORADO**

**SHEET 12 OF 14**











# LEGEND FLOOD PLAIN LIMITS



C-69 INDEX NUMBER FOR COLORADO RIVER MAPPING PROJECT  
SHEETS 1,6 AND PARTS OF 2,7,10,11  
TOPOGRAPHY COMPILED BY PHOTOGRAMMETRIC METHODS FROM  
6" C.F.L. VERTICAL AERIAL PHOTOGRAPHY TAKEN NOV. 15, 16 & 17,  
1982. BASIS OF HORIZONTAL CONTROL: THE COLORADO STATE  
PLANE COORDINATE SYSTEM, CENTRAL ZONE, LAMBERT  
CONFORMAL CONIC PROJECTION. THE FOLLOWING (USC & GS AND  
/OR USGS) TRIANGULATION STATIONS WERE USED: CATHERINE  
COORDINATES X=1,516,508.42 Y=581,255.78. GNAT-X=1,231,566.60  
Y=523,643.10. BASIS OF VERTICAL CONTROL: USC & GS SEA LEVEL  
DATUM BASED ON THE FOLLOWING BENCHMARKS: O-156 ELEVATION  
6192.284. 4870.74PS-ELEVATION 4869.860. PREPARED BY ANALYTICAL  
SURVEYS, INC. 4167 SINTON ROAD, COLORADO SPRINGS, CO. 80907.

SHEETS 3,4,5,8,9,12,13,14 AND PARTS OF 2,7,10,11  
COORDINATE SYSTEM IS THE MODIFIED COLORADO STATE PLANE  
COORDINATE SYSTEM, CENTRAL ZONE, LAMBERT CONFORMAL  
CONIC PROJECTION. THE FOLLOWING (USC & GS AND USGS)  
TRIANGULATION STATIONS WERE USED: DRY HOLLOW X=1,395,770.68,  
Y=613,033.61, CASTLE X=1,432,094.81, Y=623,300.73, ANTLER  
X=1,371,760.96, Y=630,478.31. BASIS OF VERTICAL CONTROL:  
USC & GS AND USGS. SEA LEVEL DATUM BASED ON THE FOLLOWING  
BENCHMARKS: RIFLE ELEV. 5319.199, NEW CASTLE ELEV. 5747.82.  
TOPOGRAPHY COMPILED BY PHOTOGRAMMETRIC METHODS FROM  
6" C.F.L. VERTICAL AERIAL PHOTOGRAPHY TAKEN JAN. 12, 1983.  
COMPILED BY BELL MAPPING CO., 500 KALAMATH ST. DENVER CO.



REVISION	DATE	BY
<p><b>U. S. DEPARTMENT OF AGRICULTURE</b> <b>SOIL CONSERVATION SERVICE</b></p> <p><b>FLOOD PLAINS</b> <b>FLOOD PLAIN MANAGEMENT STUDY</b> <b>TOWN OF SILT</b> <b>IN GARFIELD COUNTY</b> <b>COLORADO</b></p> <p>200 0 200 400 600 SCALE IN FEET</p> <p><b>SHEET 13 OF 14</b></p>		







E1501,000  
N546,000

E1402,000

E1403,000

E1404,000

E1405,000

E1406,000

# LEGEND FLOOD PLAIN LIMITS



GROUND ELEVATION IN FEET  
MEAN SEA LEVEL DATUM

CONTOUR INTERVAL 2.0'

CROSS SECTION

CROSS SECTION CONTINUED

INTERMITTENT STREAM


HORIZONTAL CONTROL

VERTICAL CONTROL

PHOTO CENTER


GRID POINT

100 YEAR FLOOD ELEV.



C-69 INDEX NUMBER FOR COLORADO RIVER MAPPING PROJECT  
SHEETS 1,6 AND PARTS OF 2,7,10,11  
TOPOGRAPHY COMPILED BY PHOTOGRAMMETRIC METHODS FROM  
6" C.F.L. VERTICAL AERIAL PHOTOGRAPHY TAKEN NOV. 15, 16 & 17,  
1982. BASIS OF HORIZONTAL CONTROL: THE COLORADO STATE  
PLANE COORDINATE SYSTEM, CENTRAL ZONE, LAMBERT  
CONFORMAL CONIC PROJECTION. THE FOLLOWING (USC & GS AND  
/OR USGS) TRIANGULATION STATIONS WERE USED: CATHERINE  
COORDINATES X=1,516,508.42 Y=581,255.78. GNAT-X=1,231,566.60  
Y=523,643.10. BASIS OF VERTICAL CONTROL: USC & GS SEA LEVEL  
DATUM BASED ON THE FOLLOWING BENCHMARKS: O-156 ELEVATION  
6192.284. 4870.74PS-ELEVATION 4869.860. PREPARED BY ANALYTICAL  
SURVEYS, INC. 4167 SINTON ROAD, COLORADO SPRINGS, CO. 80907.

SHEETS 3,4,5,8,9,12,13,14 AND PARTS OF 2,7,10,11  
COORDINATE SYSTEM IS THE MODIFIED COLORADO STATE PLANE  
COORDINATE SYSTEM, CENTRAL ZONE, LAMBERT CONFORMAL  
CONIC PROJECTION. THE FOLLOWING (USC & GS AND USGS)  
TRIANGULATION STATIONS WERE USED: DRY HOLLOW X=1,395,770.68,  
Y=613,033.61. CASTLE X=1,432,094.81, Y=623,300.73. ANTLER  
X=1,371,760.95, Y=630,478.31. BASIS OF VERTICAL CONTROL:  
USC & GS AND USGS. SEA LEVEL DATUM BASED ON THE FOLLOWING  
BENCHMARKS: RIFLE ELEV. 5319.199, NEW CASTLE ELEV. 5747.82.  
TOPOGRAPHY COMPILED BY PHOTOGRAMMETRIC METHODS FROM  
6" C.F.L. VERTICAL AERIAL PHOTOGRAPHY TAKEN JAN. 12, 1983.  
COMPILED BY BELL MAPPING CO., 500 KALAMATH ST. DENVER CO.




REVISION	DATE	BY

U. S. DEPARTMENT OF AGRICULTURE  
SOIL CONSERVATION SERVICE

FLOOD PLAINS  
FLOOD PLAIN MANAGEMENT STUDY  
TOWN OF SILT  
IN GARFIELD COUNTY  
COLORADO


200 0 200 400 600  
SCALE IN FEET

SHEET 14 OF 14























ELEVATION IN FEET (M.S.L.)

LEGEND

- 500 YEAR FLOOD
- 100 YEAR FLOOD
- 50 YEAR FLOOD
- 10 YEAR FLOOD
- STREAM BED



U. S. DEPARTMENT OF AGRICULTURE  
SOIL CONSERVATION SERVICE

FLOOD PROFILES  
FLOOD PLAIN MANAGEMENT STUDY  
TOWN OF SILT  
IN GARFIELD COUNTY  
COLORADO

EAST WATERSHED  
SHEET 3 OF 23

FEET UPSTREAM OF LOWER STUDY LIMIT





ELEVATION IN FEET (M.S.L.)

LEGEND


- 500 YEAR FLOOD
- 100 YEAR FLOOD
- 50 YEAR FLOOD
- 10 YEAR FLOOD
- STREAM BED

FEET UPSTREAM OF LOWER STUDY LIMIT

U. S. DEPARTMENT OF AGRICULTURE  
SOIL CONSERVATION SERVICE

FLOOD PROFILES  
FLOOD PLAIN MANAGEMENT STUDY  
TOWN OF SILT  
IN GARFIELD COUNTY  
COLORADO


EAST WATERSHED  
SHEET 4 OF 23
















ELEVATION IN FEET (M.S.L.)

LEGEND

- 500 YEAR FLOOD
- - - 100 YEAR FLOOD
- . - . 50 YEAR FLOOD
- - - 10 YEAR FLOOD
- /// STREAM BED




U. S. DEPARTMENT OF AGRICULTURE  
SOIL CONSERVATION SERVICE

FLOOD PROFILES  
FLOOD PLAIN MANAGEMENT STUDY  
TOWN OF SILT  
IN GARFIELD COUNTY  
COLORADO

SIXTEENTH ST WATERSHED  
SHEET 6 OF 23


































ELEVATION IN FEET (M.S.L.)

LEGEND

- 500 YEAR FLOOD
- - - - 100 YEAR FLOOD
- · - · 50 YEAR FLOOD
- - - - 10 YEAR FLOOD
- ////// STREAM BED



U. S. DEPARTMENT OF AGRICULTURE  
SOIL CONSERVATION SERVICE


FLOOD PROFILES  
FLOOD PLAIN MANAGEMENT STUDY  
TOWN OF SILT  
IN GARFIELD COUNTY  
COLORADO

SEVENTH ST WATERSHED  
SHEET 11 OF 23

FEET UPSTREAM OF LOWER STUDY LIMIT







LEGEND

- 500 YEAR FLOOD
- 100 YEAR FLOOD
- 50 YEAR FLOOD
- 10 YEAR FLOOD
- STREAM BED

U. S. DEPARTMENT OF AGRICULTURE  
SOIL CONSERVATION SERVICE

FLOOD PROFILES  
FLOOD PLAIN MANAGEMENT STUDY  
TOWN OF SILT  
IN GARFIELD COUNTY  
COLORADO

SEVENTH ST WATERSHED  
SHEET 12 OF 23






ELEVATION IN FEET (M.S.L.)

LEGEND

- 500 YEAR FLOOD
- - - 100 YEAR FLOOD
- - - 50 YEAR FLOOD
- - - 10 YEAR FLOOD
- /// STREAM BED



U. S. DEPARTMENT OF AGRICULTURE  
SOIL CONSERVATION SERVICE

FLOOD PROFILES  
FLOOD PLAIN MANAGEMENT STUDY  
TOWN OF SILT  
IN GARFIELD COUNTY  
COLORADO

FIRST ST WATERSHED  
SHEET 13 OF 23

FEET UPSTREAM OF LOWER STUDY LIMIT






ELEVATION IN FEET (M.S.L.)

LEGEND

- 500 YEAR FLOOD
- 100 YEAR FLOOD
- 50 YEAR FLOOD
- 10 YEAR FLOOD
- STREAM BED



U. S. DEPARTMENT OF AGRICULTURE  
SOIL CONSERVATION SERVICE


FLOOD PROFILES  
FLOOD PLAIN MANAGEMENT STUDY  
TOWN OF SILT  
IN GARFIELD COUNTY  
COLORADO

FIRST ST. WATERSHED  
SHEET 14 OF 23





















ELEVATION IN FEET (M.S.L.)

LEGEND

- 500 YEAR FLOOD
- 100 YEAR FLOOD
- 50 YEAR FLOOD
- 10 YEAR FLOOD
- STREAM BED




U. S. DEPARTMENT OF AGRICULTURE  
SOIL CONSERVATION SERVICE

FLOOD PROFILES  
FLOOD PLAIN MANAGEMENT STUDY  
TOWN OF SILT  
IN GARFIELD COUNTY  
COLORADO

FIRST ST WATERSHED  
SHEET 17 OF 23












ELEVATION IN FEET (M.S.L.)

LEGEND

- 500 YEAR FLOOD
- - - 100 YEAR FLOOD
- · - · 50 YEAR FLOOD
- - - 10 YEAR FLOOD
- /// STREAM BED



U. S. DEPARTMENT OF AGRICULTURE  
SOIL CONSERVATION SERVICE


FLOOD PROFILES  
FLOOD PLAIN MANAGEMENT STUDY  
TOWN OF SILT  
IN GARFIELD COUNTY  
COLORADO

WEST WATERSHED  
SHEET 19 OF 23

FEET UPSTREAM OF LOWER STUDY LIMIT


























ELEVATION IN FEET (M.S.L.)

LEGEND

- 500 YEAR FLOOD
- 100 YEAR FLOOD
- 50 YEAR FLOOD
- 10 YEAR FLOOD
- STREAM BED



U. S. DEPARTMENT OF AGRICULTURE  
SOIL CONSERVATION SERVICE


FLOOD PROFILES  
FLOOD PLAIN MANAGEMENT STUDY  
TOWN OF SILT  
IN GARFIELD COUNTY  
COLORADO

WEST WATERSHED  
SHEET 23 OF 23

FEET UPSTREAM OF LOWER STUDY LIMIT








TYPICAL VALLEY CROSS-SECTION  
TOWN OF SILT FLOOD PLAIN MANAGEMENT STUDY


Figure 1






TYPICAL VALLEY CROSS-SECTION  
TOWN OF SILT FLOOD PLAIN MANAGEMENT STUDY

Figure 2




TYPICAL VALLEY CROSS-SECTION  
TOWN OF SALT FLOOD PLAIN MANAGEMENT STUDY  
Figure 3





TYPICAL VALLEY CROSS-SECTION  
TOWN OF SILT FLOOD PLAIN MANAGEMENT STUDY

Figure 4



TYPICAL VALLEY CROSS-SECTION  
TOWN OF SILT FLOOD PLAIN MANAGEMENT STUDY

Figure 5





TABLE 1 FLOOD FREQUENCY-ELEVATION AND DISCHARGE DATA \*

Cross Section Design- nation	Stationing from Mouth	Feet	Identification	Stream Bed Elevation	10-Year Flood	50-Year Flood	100-Year Flood	500-Year Flood
513 #	0+00		Colorado River at East Watershed	5417.7	5426.7 20100	5426.7 20100	5426.7 20100	5426.7 20100
1970	5+20			5426.9	5429.1 96	5429.2 279	5429.2 381	5429.2 658
1972.1	6+50			5430.5	5431.7 96	5432.7 279	5433.0 381	5433.5 658
1972.2	7+98		Interstate 70	5430.5	5432.8 96	5433.8 279	5434.2 381	5434.9 658
1974.1	19+78			5438.0	5440.2 96	5441.7 279	5441.8 381	5442.1 658
1974.2	20+38		Denver & Rio Grande Western R.R.	5438.0	5440.4 96	5441.8 279	5441.9 381	5442.2 658
1976	21+53			5438.0	5441.4 96	5441.9 279	5442.0 381	5442.3 658
1978	26+08			5443.8	5444.1 96	5444.2 279	5444.3 381	5444.5 658
1980.1	26+58			5447.3	5449.8 96	5450.1 279	5450.2 381	5450.3 658
1980.2	27+08		U.S. Highway 6 Main St	5447.3	5449.9 96	5450.3 279	5450.4 381	5450.7 658
1982	34+58			5450.0	5452.4 59	5453.3 162	5453.6 215	5454.2 352
1984	39+88		Lower Castle Valley Ditch	5471.5	5471.9 59	5472.1 162	5472.2 215	5472.4 352
1986	44+88			5487.0	5487.4 59	5487.6 162	5487.7 215	5487.8 352

\* Flood elevations pertain to the primary channel and usually remain constant in a lateral direction across the flood plain. However, flood elevations in the outer portions of a cross section may differ from the primary channel due to road crossings, upstream diversions, etc.

# Discharge in Colorado River at 25 year frequency

Divided flow exists with 2/3 of discharge at this location



TABLE 1  
FLOOD FREQUENCY-ELEVATION AND DISCHARGE DATA \*

Cross Section Design- nation	Stationing from Mouth	Identification	Stream Bed Elevation	Feet	10-Year Flood	50-Year Flood	100-Year Flood	Crest-Elevation and Peak Discharge c.f.s.	500-Year Flood
1988	50+48		5511.0	59	5511.4	5511.5	5511.6	5511.8	5511.8
									352
1990	53+28		5525.0	59	5525.7	5526.0	5526.1	5526.4	5526.4
									352
1992	64+78		5568.0	59	5568.4	5568.7	5568.8	5569.1	5569.1
									352
1994	71+38		5593.0	59	5594.4	5595.0	5595.3	5595.8	5595.8
									352
1996.1	71+78		5595.0	59	5597.9	5599.5	5599.7	5600.1	5600.1
									352
1996.2	72+08	Road	5595.0	59	5599.3	5599.9	5600.1	5600.6	5600.6
									352
1998	72+28		5596.0	59	5599.4	5600.1	5600.3	5600.9	5600.9
									352
2000	78+28		5618.5	59	5619.5	5620.1	5620.2	5620.6	5620.6
									352
2001	87+58		5653.3	59	5654.3	5654.8	5655.0	5655.4	5655.4
									352
2002	94+18		5671.9	59	5674.0	5675.0	5675.3	5676.1	5676.1
									352
2003	94+78		5680.0	59	5680.7	5681.1	5681.3	5681.7	5681.7
									352
2004	103+28		5709.8	62	5710.7	5711.3	5711.5	5712.0	5712.0
									337
2005	113+38		5749.8	62	5750.5	5750.9	5751.1	5751.4	5751.4
									337

\* Flood elevations pertain to the primary channel and usually remain constant in a lateral direction across the flood plain. However, flood elevations in the outer portions of a cross section may differ from the primary channel due to road crossings, upstream diversions, etc.

TABLE 1

## FLOOD FREQUENCY-ELEVATION AND DISCHARGE DATA \*

Cross Section Stationing from Mouth	Identification	Stream Bed Elevation	10-Year Flood	50-Year Flood	100-Year Flood	500-Year Flood
Design- nation		Feet				
2006		5776.0	5776.4	5776.7	5776.8	5777.1
			62	161	210	337
2007.1		5776.5	5778.9	5780.9	5781.8	5784.2
			62	161	210	337
2007.2	County Rd 214	5776.5	5780.3	5780.9	5781.8	5784.2
			62	161	210	337
2008		5782.0	5782.5	5783.3	5784.4	5784.5
			62	161	210	337
2009		5823.5	5824.2	5824.6	5824.7	5825.0
			62	161	210	337
2010		5870.2	5871.6	5872.3	5872.5	5873.0
			62	161	210	337
2011	Confluence with Tributary	5913.9	5915.0	5915.5	5915.6	5916.0
			62	161	210	337
2012		5939.8	5940.8	5941.3	5941.4	5941.8
			22	64	83	135
2013	Upper Study Limit	5963.2	5964.0	5964.4	5964.5	5964.9
			22	64	83	135

\* Flood elevations pertain to the primary channel and usually remain constant in a lateral direction across the flood plain. However, flood elevations in the outer portions of a cross section may differ from the primary channel due to road crossings, upstream diversions, etc.



TABLE 1 FLOOD FREQUENCY-ELEVATION AND DISCHARGE DATA \*

Cross Section Design- nation	Stationing from Mouth Feet	Identification	Stream Bed Elevation	10-Year Flood	50-Year Flood	100-Year Flood	500-Year Flood
2011	153+48	East Watershed Trib	5913.9	5915.0 62	5915.5 161	5915.6 210	5916.0 337
2014	161+08		5948.8	5950.1 63	5950.7 150	5950.9 190	5951.4 297
2015	168+68		5984.0	5985.6 63	5986.3 150	5986.5 190	5987.0 297
2016	178+38		6032.1	6033.7 63	6034.3 150	6034.5 190	6035.0 297
2017	187+18		6080.0	6081.6 69	6082.2 152	6082.4 190	6082.8 289
2018	196+58	Upper Study Limit	6128.2	6129.7 69	6130.3 152	6130.5 190	6130.9 289

\* Flood elevations pertain to the primary channel and usually remain constant in a lateral direction across the flood plain. However, flood elevations in the outer portions of a cross section may differ from the primary channel due to road crossings, upstream diversions, etc.

TABLE 1

## FLOOD FREQUENCY-ELEVATION AND DISCHARGE DATA \*

Cross Section-- Stationing from Mouth	Identification	Stream Bed Elevation	Feet	10-Year Flood	50-Year Flood	100-Year Flood	500-Year Flood
513 #	Colorado River at Sixteenth St Watersh	5417.7	5426.7 20100	5426.7 20100	5426.7 20100	5426.7 20100	5426.7 20100
1970	Sixteenth St Watershed	5426.9	5429.1 96	5429.2 279	5429.2 381	5429.2 657	5429.2 657
1972.1		5430.5	5431.7 96	5432.7 279	5433.0 381	5433.5 657	5433.5 657
1972.2	Interstate 70	5430.5	5432.8 96	5433.8 279	5434.2 381	5434.9 657	5434.9 657
1974.1		5438.0	5440.2 96	5441.7 279	5441.8 381	5442.1 657	5442.1 657
1974.2	Denver & Rio Grande Western R.R.	5438.0	5440.4 96	5441.8 279	5441.9 381	5442.2 657	5442.2 657
1976		5438.0	5441.4 96	5441.9 279	5442.0 381	5442.3 657	5442.3 657
1978		5443.8	5444.1 96	5444.2 279	5444.3 381	5444.5 657	5444.5 657
1980.1		5447.3	5449.8 96	5450.1 279	5450.2 381	5450.3 657	5450.3 657
1980.2	U.S. Highway 6 Main St	5447.3	5449.9 96	5450.3 279	5450.4 381	5450.7 657	5450.7 657
2980		5453.5	5454.5 60	5455.1 178	5455.3 237	5455.7 397	5455.7 397
2982		5459.0	5459.9 60	5460.3 178	5460.4 237	5460.7 397	5460.7 397
2984	Lower Castle Valley Ditch	5469.0	5469.2 60	5469.4 178	5469.5 237	5469.7 397	5469.7 397

\* Flood elevations pertain to the primary channel and usually remain constant in a lateral direction across the flood plain. However, flood elevations in the outer portions of a cross section may differ from the primary channel due to road crossings, upstream diversions, etc.

# Discharge in Colorado River at 25 year frequency

Divided flow exists with 2/3 of discharge at this location



TABLE 1  
FLOOD FREQUENCY-ELEVATION AND DISCHARGE DATA \*

Cross Section Station- nation	Stationing from Mouth Feet	Identification	Stream Bed Elevation Feet	10-Year Flood	50-Year Flood	100-Year Flood	Crest-Elevation and Peak Discharge c.f.s.
2986	42+33	Grand Ave	5479.7	5480.1 60	5480.2 178	5480.3 237	5480.4 397
2988	47+33		5495.8	5497.0 60	5497.8 178	5498.1 237	5498.8 397
2990	51+33		5507.0	5507.9 60	5508.1 178	5508.2 237	5508.5 397
2992	56+73		5531.0	5531.8 74	5532.1 197	5532.3 257	5532.5 420
2994	65+73		5560.5	5561.5 74	5562.0 197	5562.2 257	5562.6 420
2996	73+93		5583.5	5584.4 74	5584.9 197	5585.1 257	5585.5 420
2998	81+93		5608.5	5609.9 74	5610.6 197	5610.9 257	5611.5 420
3000	91+93		5649.5	5650.5 74	5651.1 197	5651.3 257	5651.9 420
3001	101+73		5702.0	5703.1 74	5703.7 197	5703.9 257	5704.2 420
3002	108+73		5735.0	5735.7 74	5736.1 197	5736.2 257	5736.4 420
3003.1	108+93		5736.0	5740.0 74	5743.5 197	5744.7 257	5744.8 420
3003.2	109+33	County Rd 214	5736.0	5744.0 74	5744.5 197	5745.0 257	5745.2 420
3004	109+58		5739.5	5744.5 74	5744.7 197	5745.0 257	5745.2 420

\* Flood elevations pertain to the primary channel and usually remain constant in a lateral direction across the flood plain. However, flood elevations in the outer portions of a cross section may differ from the primary channel due to road crossings, upstream diversions, etc.

TABLE 1 FLOOD FREQUENCY-ELEVATION AND DISCHARGE DATA \*

Cross Section Designation	Stationing from Mouth	Identification	Stream Bed Elevation	Feet	10-Year Flood	50-Year Flood	100-Year Flood	Crest-Elevation and Peak Discharge c.f.s.	500-Year Flood
3005	116+58	Tributary confluence	5759.4	74	5760.5	5761.2	5761.5	5762.1	420
3006	122+98		5796.0		5796.6	5797.1	5797.3	5797.7	79
3007.1	123+88		5806.5		5807.6	5809.8	5809.9	5810.1	79
3007.2	124+28	Private Rd	5806.5		5808.4	5809.9	5810.1	5810.2	79
3008	125+28		5808.0		5808.6	5810.0	5810.1	5810.4	79
3009	127+48		5816.0		5816.6	5817.1	5817.3	5817.7	79
3010.1	128+23		5822.5		5823.2	5824.5	5825.1	5826.7	79
3010.2	128+58	County Rd 250	5822.5		5823.4	5825.7	5828.7	5829.4	79
3011	129+18		5825.0		5825.5	5826.5	5829.0	5830.1	79
3012	132+88		5840.0		5840.3	5840.7	5840.9	5841.4	79
3013	142+88		5895.0		5895.5	5896.0	5896.2	5896.7	79
3014	151+38	Upper Study Limit	5939.9		5940.1	5940.4	5940.6	5940.9	79

\* Flood elevations pertain to the primary channel and usually remain constant in a lateral direction across the flood plain. However, flood elevations in the outer portions of a cross section may differ from the primary channel due to road crossings, upstream diversions, etc.



TABLE 1 FLOOD FREQUENCY-ELEVATION AND DISCHARGE DATA \*

Cross Section- nation	Stationing from Mouth Feet	Identification	Stream Bed Elevation Feet	10-Year Flood	50-Year Flood	100-Year Flood	500-Year Flood
3005	116+58	Sixteenth St Trib	5759.4	5760.5 74	5761.2 197	5761.5 257	5762.1 420
3015	126+58		5799.7	5801.0 71	5801.7 186	5801.9 242	5802.4 391
3016	132+38		5821.7	5822.8 71	5823.6 186	5823.9 242	5824.5 391
3017	142+58		5870.0	5871.4 70	5872.4 166	5872.7 211	5873.5 329
3018	152+38		5915.0	5916.4 70	5917.0 166	5917.3 211	5917.9 329
3019	159+38		5854.3	5855.5 70	5956.0 166	5856.2 211	5956.6 329
3020	168+58	Upper Study Limit	6003.5	6004.4 70	6004.9 166	6005.1 211	6005.5 329

\* Flood elevations pertain to the primary channel and usually remain constant in a lateral direction across the flood plain. However, flood elevations in the outer portions of a cross section may differ from the primary channel due to road crossings, upstream diversions, etc.

TABLE 1 FLOOD FREQUENCY-ELEVATION AND DISCHARGE DATA \*

Cross Section- nation	Stationing from Mouth Feet	Identification	Stream Red Elevation	10-Year Flood	50-Year Flood	100-Year Flood	Crest-Elevation and Peak Discharge c.f.s.
488	0+00	Colorado River at Seventh St Watershed	5402.5	5410.2 10100	5410.2 10100	5410.2 10100	
3948	11+40	Seventh St Watershed	5413.9	5414.0 60	5414.0 101	5414.1 139	
3950.1	15+50		5419.8	5422.2 60	5422.9 101	5423.1 139	
3950.2	16+40	Frontage Rd	5419.8	5423.0 60	5423.2 101	5423.4 139	
3952	19+60	Interstate 70 Ramp	5423.5	5424.0 60	5424.1 101	5424.2 139	
3954	29+10	Interstate 70	5420.8	5424.0 60	5424.1 101	5424.2 139	
6000	30+50	Interstate 70	5422.5	5424.0 6	5424.1 32	5424.2 53	
6002	34+30	Interstate 70 Ramp	5423.2	5424.0 6	5424.1 32	5424.2 53	
6004	38+90		5422.5	5424.0 6	5424.2 32	5424.3 53	
6004.2	39+70	Denver & Rio Grande Western R.R.	5422.5	5424.0 6	5425.3 32	5426.9 53	
6005	42+90	East Segment of Divided flow reach	5425.0	5425.3 2	5426.0 9	5427.2 13	
6006	44+10		5436.3	5436.5 2	5436.6 9	5436.7 13	
6007	46+30		5443.0	5443.2 2	5443.3 9	5443.4 13	

\* Flood elevations pertain to the primary channel and usually remain constant in a lateral direction across the flood plain. However, flood elevations in the outer portions of a cross section may differ from the primary channel due to road crossings, upstream diversions, etc.

# Discharge in Colorado River at 25 year frequency  
Divided flow exists with 1/3 of discharge at this location



TABLE 1  
FLOOD FREQUENCY-ELEVATION AND DISCHARGE DATA \*

Cross Section nation	Stationing from Mouth Feet	Identification	Stream Bed Elevation Feet	10-Year Flood	50-Year Flood	100-Year Flood	500-Year Flood
6008	48+60		5445.8	5446.0	5446.2	5446.3	5446.5
6009	52+60	Grand Ave	5454.8	5454.9	5454.9	5454.9	5455.0
6010	55+80	Ballard Ave	5461.5	5461.6	5461.7	5461.8	5461.9
6015	59+20	Orchard Ave End Divided Flow	5474.1	5474.2	5474.3	5474.3	5474.4
6004.2	39+70	Denver & Rio Grande Western R.R.	5422.5	5424.0	5425.3	5426.9	5428.3
6011	44+10	West Segment of Divided flow reach	5442.0	5442.2	5442.4	5442.5	5442.6
6012	47+10	Home Ave	5449.5	5449.7	5449.8	5449.8	5449.9
6013	50+40	Grand Ave	5455.5	5455.7	5455.9	5456.0	5456.2
6014	55+40	Lower Cactus Valley Ditch	5469.0	5469.1	5469.1	5469.1	5469.1
6015	58+80	Orchard Ave End Divided Flow	5474.1	5474.2	5474.3	5474.3	5474.4
6016	64+00		5491.8	5491.9	5492.0	5492.1	5492.2
6018	74+40	Upper Study Limit	5531.5	5531.8	5532.1	5532.2	5532.5

\* Flood elevations pertain to the primary channel and usually remain constant in a lateral direction across the flood plain. However, flood elevations in the outer portions of a cross section may differ from the primary channel due to road crossings, upstream diversions, etc.

TABLE 1 FLOOD FREQUENCY-ELEVATION AND DISCHARGE DATA \*

Cross Section- station	Stationing from Mouth	Feet	Identification	Stream Bed Elevation	10-Year Flood	50-Year Flood	100-Year Flood	500-Year Flood
488 #	0+00		Colorado River at First St Watershed	5402.5	5410.2 10100	5410.2 10100	5410.2 10100	5410.2 10100
3948	11+40		First St Watershed	5413.9	5414.0 60	5414.0 101	5414.1 139	5414.1 300
3950.1	15+50			5419.8	5422.2 60	5422.9 101	5423.1 139	5423.3 300
3950.2	16+40		Frontage Rd	5419.8	5423.0 60	5423.2 101	5423.4 139	5423.4 300
3952	19+60		Interstate 70 Ramp	5423.5	5424.0 60	5424.1 101	5424.2 139	5424.4 300
3954	29+10		Interstate 70	5420.8	5424.0 60	5424.1 101	5424.2 139	5424.5 300
3956	39+40			5421.5	5424.0 58	5424.1 98	5424.2 143	5424.4 305
3958	47+00		Interstate 70 Ramp	5427.4	5427.6 58	5427.6 98	5427.7 143	5427.8 305
3960	54+00			5423.5	5427.7 58	5427.7 98	5427.8 143	5428.1 305
3962	59+00			5437.5	5438.1 58	5438.2 98	5438.4 143	5438.8 305
3964.1	59+30			5435.7	5438.5 58	5438.7 98	5439.5 143	5441.7 305
3964.2	59+73		Denver & Rio Grande Western R.R.	5435.7	5438.6 58	5439.4 98	5439.7 143	5441.8 305
3966	60+80			5439.5	5440.9 58	5441.4 98	5442.1 143	5442.3 305

\* Flood elevations pertain to the primary channel and usually remain constant in a lateral direction across the flood plain. However, flood elevations in the outer portions of a cross section may differ from the primary channel due to road crossings, upstream diversions, etc.

# Discharge in Colorado River at 25 year frequency

Divided flow exists with 1/3 of discharge at this location



TABLE 1

## FLOOD FREQUENCY-ELEVATION AND DISCHARGE DATA \*

Cross Section Design- nation	Stationing from Mouth Feet	Identification	Stream Bed Elevation	10-Year Flood	50-Year Flood	100-Year Flood	Crest-Elevation and Peak Discharge c.f.s.
3968.1	61+70		5441.0	5443.8 64	5446.4 178	5449.0 250	5449.2 463
3968.2	62+30	Main St	5441.0	5445.2 64	5448.9 178	5449.1 250	5449.4 463
3970	63+20		5447.5	5448.1 64	5449.3 178	5449.4 250	5449.7 463
3972.1	64+70		5451.0	5454.5 64	5456.2 178	5456.3 250	5456.5 463
3972.2	65+32	Home Ave	5451.0	5456.2 64	5456.3 178	5456.4 250	5456.7 463
3974	69+20		5459.0	5459.7 64	5460.5 178	5460.7 250	5461.2 463
3976	70+20	Lower Cactus Valley Ditch	5466.0	5466.5 64	5466.9 178	5467.1 250	5467.5 463
3978	75+40		5473.2	5474.2 64	5474.7 178	5475.0 250	5475.5 463
3980	81+00		5487.5	5488.6 64	5489.4 178	5489.8 250	5490.8 463
3982.1	81+58		5485.3	5490.1 107	5494.3 353	5494.5 488	5494.8 899
3982.2	81+82	Road	5485.3	5493.2 107	5494.6 353	5494.9 488	5495.3 899
3984	83+10		5493.0	5494.5 107	5495.4 353	5495.6 488	5496.2 899
3986.1	83+65		5496.5	5500.4 107	5501.1 353	5501.3 488	5501.9 899

\* Flood elevations pertain to the primary channel and usually remain constant in a lateral direction across the flood plain. However, flood elevations in the outer portions of a cross section may differ from the primary channel due to road crossings, upstream diversions, etc.

TABLE 1 FLOOD FREQUENCY-ELEVATION AND DISCHARGE DATA \*

Cross Section Design- nation	Stationing from Mouth Feet	Identification	Stream Bed Elevation	10-Year Flood	50-Year Flood	100-Year Flood	500-Year Flood
3986.2	84+25	County Rd 231	5496.5	5500.7 107	5501.5 353	5501.8 488	5502.4 899
3988	84+70		5496.2	5500.8 107	5501.7 353	5502.0 488	5502.6 899
3990	90+30		5507.5	5508.6 107	5509.8 353	5510.2 488	5511.4 899
3992	98+90		5530.5	5531.7 107	5532.8 353	5533.3 488	5534.2 899
3994	103+10		5539.0	5540.4 107	5541.4 353	5541.9 488	5543.0 899
3996.1	103+72		5535.2	5541.2 107	5542.8 353	5543.4 488	5544.7 899
3996.2	103+88	Private Rd	5535.2	5541.4 107	5543.3 353	5543.9 488	5545.4 899
3998	104+50		5541.5	5543.1 107	5544.5 353	5545.1 488	5546.5 899
4000	107+30		5549.5	5550.7 107	5551.8 353	5552.3 488	5553.4 899
4001	121+30		5589.0	5591.6 107	5593.2 353	5593.6 488	5594.5 899
4002	131+70		5617.8	5619.8 107	5620.9 353	5621.4 488	5622.5 899
4003	136+30		5633.5	5635.6 107	5637.4 353	5638.2 488	5639.8 899
4004.1	137+15		5635.6	5637.9 122	5640.7 415	5641.8 565	5644.4 982

\* Flood elevations pertain to the primary channel and usually remain constant in a lateral direction across the flood plain. However, flood elevations in the outer portions of a cross section may differ from the primary channel due to road crossings, upstream diversions, etc.



TABLE 1

## FLOOD FREQUENCY-ELEVATION AND DISCHARGE DATA \*

Cross Section Design- nation	Stationing from Mouth Feet	Identification	Stream Bed Elevation Feet	10-Year Flood	50-Year Flood	100-Year Flood	Peak Discharge c.f.s.
4004.2	137+75	Road	5635.6	5645.3 122	5649.1 415	5649.4 565	5650.3 982
4006	142+20		5647.5	5648.7 122	5649.7 415	5650.1 565	5651.0 982
4007	147+80		5664.0	5665.7 122	5666.8 415	5667.2 565	5668.2 982
4008	151+80	Trib Confluence	5679.7	5681.0 115	5682.1 372	5682.4 501	5683.2 860
4009	157+40		5699.0	5700.1 50	5700.8 160	5701.1 215	5701.8 365
4010.1	157+70		5703.1	5707.9 50	5710.0 160	5710.0 215	5710.1 365
4010.2	158+10	County Rd 261	5703.1	5710.1 50	5710.1 160	5710.2 215	5710.3 365
4011	158+40		5710.0	5710.3 50	5710.6 160	5710.7 215	5711.0 365
4012	162+00	Upper Study Limit	5714.9	5716.2 50	5716.8 160	5717.0 215	5717.5 365

\* Flood elevations pertain to the primary channel and usually remain constant in a lateral direction across the flood plain. However, flood elevations in the outer portions of a cross section may differ from the primary channel due to road crossings, upstream diversions, etc.

FLOOD FREQUENCY-ELEVATION AND DISCHARGE DATA \*

Cross	Stationing	Identification	Stream Bed Elevation	10-Year Flood	50-Year Flood	100-Year Flood	Crest-Elevation and Peak Discharge c.f.s.
Design- nation	from Mouth  Feet		Feet	Flood	Flood	Flood	500-Year Flood
4008	151+80	First St Watershed Tributary	5679.7	5681.0 115	5682.1 372	5682.4 501	5683.2 860
4013	160+60		5710.0	5712.0 66	5713.2 207	5713.6 277	5715.5 797
4014	170+20		5747.7	5748.2 66	5748.7 207	5748.8 277	5749.8 797
4015	179+20		5776.8	5778.2 66	5779.1 207	5779.5 277	5781.3 797
4016	191+60		5829.8	5831.2 66	5832.0 207	5832.3 277	5833.7 797
4017	204+80		5881.3	5882.4 66	5883.3 207	5883.7 277	5885.7 797
4017.4	205+60		5892.8	5898.2 66	5900.5 207	5900.6 277	5901.2 797
4017.5	206+05	County Rd 228	5892.8	5900.7 66	5900.8 207	5900.9 277	5901.8 797
4018	207+60		5896.0	5900.9 20	5901.0 64	5901.2 86	5902.3 143
4020.1	210+60		5820.5	5922.1 20	5925.4 64	5925.6 86	5825.8 143
4020.2	211+00	County Rd 250	5920.5	5922.7 20	5925.6 64	5925.8 86	5926.0 143
4022	212+20	Upper Study Limit	5922.0	5923.4 20	5925.8 64	5925.9 86	5926.2 143

\* Flood elevations pertain to the primary channel and usually remain constant in a lateral direction across the flood plain. However, flood elevations in the outer portions of a cross section may differ from the primary channel due to road crossings, upstream diversions, etc.



TABLE 1  
FLOOD FREQUENCY-ELEVATION AND DISCHARGE DATA \*

Cross Section Design- nation	Stationing from Mouth Feet	Identification	Stream Bed Elevation Feet	10-Year Flood	50-Year Flood	100-Year Flood	500-Year Flood
481#	0+00	Colorado River at West Watershed	5383.6	5393.1 30200	5393.1 30200	5393.1 30200	5393.1 30200
4978	14+60	West Watershed	5392.0	5394.9 169	5395.0 463	5395.0 633	5395.0 1032
4980	18+40		5399.8	5401.1 169	5403.2 463	5403.7 633	5403.5 1032
4986.1	18+60		5409.8	5412.2 169	5414.4 463	5415.5 633	5417.7 1032
4986.2	21+00	Denver & Rio Grande Western R.R.	5409.8	5412.4 169	5415.0 463	5416.7 633	5418.6 1032
4988	21+30		5409.5	5413.4 169	5416.8 463	5418.4 633	5421.7 1032
4990	29+50		5434.0	5436.8 169	5438.2 463	5438.7 633	5439.7 1032
4992	39+20		5467.1	5468.0 169	5468.8 463	5469.1 633	5469.8 1032
4994.1	39+50		5467.1	5468.3 169	5468.7 463	5470.0 633	5472.7 1032
4994.2	40+30	Road	5467.1	5469.3 169	5477.5 463	5487.0 533	5490.6 1032
4996	40+50		5469.4	5470.4 169	5477.9 463	5487.3 633	5491.0 1032
4998	51+70		5492.8	5494.8 169	5495.9 463	5496.3 633	5497.2 1032
5000	64+10		5521.5	5523.4 169	5524.6 463	5525.1 633	5526.1 1032

\* Flood elevations pertain to the primary channel and usually remain in a lateral direction across the flood plain. However, flood elevations in the outer portions of a cross section may differ from the primary channel due to road crossings, upstream diversions, etc.

# Discharge in Colorado River at 25 year frequency

TABLE 1 FLOOD FREQUENCY-ELEVATION AND DISCHARGE DATA \*

Cross Section Design- nation	Stationing from Mouth Feet	Identification	Stream Bed Elevation	10-Year Flood	50-Year Flood	100-Year Flood	500-Year Flood
5001	73+90		5547.0	5549.2 169	5550.3 463	5550.7 633	5551.6 1032
5002	84+30		5576.0	5577.8 175	5578.6 477	5579.0 638	5579.7 1030
5003	93+10		5595.6	5597.1 175	5598.1 477	5598.5 638	5599.3 1030
5004	101+10		5617.5	5618.9 175	5619.6 477	5619.9 638	5620.3 1030
5005.1	101+30		5617.0	5620.1 175	5623.0 477	5624.3 638	5626.9 1030
5005.2	101+60	County Rd 233	5617.0	5620.5 175	5625.3 477	5626.1 638	5632.1 1030
5006	101+80		5619.0	5621.8 175	5626.9 477	5628.5 638	5632.1 1030
5007	111+00		5645.0	5446.4 175	5647.1 477	5647.3 638	5647.7 1030
5008	119+80		5665.8	5667.1 175	5667.8 477	5668.1 638	5668.5 1030
5009	129+40		5691.7	5693.5 202	5694.5 529	5694.9 690	5695.5 1052
5010	138+60		5713.0	5714.7 202	5715.8 529	5716.2 690	5716.9 1052
5011	147+20		5738.7	5740.0 71	5740.7 206	5740.9 275	5741.4 391
5012	159+00		5744.3	5775.6 71	5776.2 206	5776.4 275	5776.8 391

\* Flood elevations pertain to the primary channel and usually remain constant in a lateral direction across the flood plain. However, flood elevations in the outer portions of a cross section may differ from the primary channel due to road crossings, upstream diversions, etc.



TABLE 1 FLOOD FREQUENCY-ELEVATION AND DISCHARGE DATA \*

Cross Section- nation	Stationing from Mouth	Identification	Stream Bed Elevation	Feet	10-Year Flood	50-Year Flood	100-Year Flood	Crest-Elevation and Peak Discharge c.f.s.
5013	170+40		5814.0		5814.8	5815.3	5815.4	5815.7
					71	206	275	391
5014	179+20		5839.1		5840.5	5841.3	5841.7	5842.2
					71	206	275	391
5015	183+20		5855.0		5856.4	5857.4	5857.8	5858.4
					71	206	275	391
5016.1	183+65		5857.5		5861.4	5862.3	5862.4	5862.5
					71	206	275	391
5016.2	184+25	County Rd 237	5857.5		5863.3	5862.5	5862.6	5862.7
					71	206	275	391
5017	184+45		5862.1		5863.2	5863.7	5863.9	5864.2
					71	206	275	391
5018	194+05		5890.0		5890.9	5891.2	5891.4	5891.6
					50	114	144	221
5019	203+05		5928.0		5929.3	5929.9	5930.0	5930.4
					50	114	144	221
5020	211+25		5966.2		5967.3	5967.7	5967.9	5968.2
					50	114	144	221
5021	219+45	Upper Study Limit	6004.0		6004.9	6005.2	6005.3	6005.6
					50	114	144	221

\* Flood elevations pertain to the primary channel and usually remain constant in a lateral direction across the flood plain. However, flood elevations in the outer portions of a cross section may differ from the primary channel due to road crossings, upstream diversions, etc.







SOIL CONSERVATION SERVICE